

# PIC12F629/675 Data Sheet

8-Pin, Flash-Based 8-Bit CMOS Microcontrollers

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our
  knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data
  Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

#### Trademarks

The Microchip name and logo, the Microchip logo, dsPIC, Keeloq, Keeloq logo, MPLAB, PIC, PICmicro, PICSTART, PIC<sup>32</sup> logo, rfPIC and UNI/O are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

FilterLab, Hampshire, HI-TECH C, Linear Active Thermistor, MXDEV, MXLAB, SEEVAL and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, dsSPEAK, ECAN, ECONOMONITOR, FanSense, HI-TIDE, In-Circuit Serial Programming, ICSP, Mindi, MiWi, MPASM, MPLAB Certified logo, MPLIB, MPLINK, mTouch, Octopus, Omniscient Code Generation, PICC, PICC-18, PICDEM, PICDEM.net, PICkit, PICtail, REAL ICE, rfLAB, Select Mode, Total Endurance, TSHARC, UniWinDriver, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2010, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

ISBN: 978-1-60932-160-4

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

QUALITY MANAGEMENT SYSTEM

CERTIFIED BY DNV

ISO/TS 16949:2002



### 8-Pin Flash-Based 8-Bit CMOS Microcontroller

#### **High-Performance RISC CPU:**

- · Only 35 Instructions to Learn
  - All single-cycle instructions except branches
- · Operating Speed:
  - DC 20 MHz oscillator/clock input
  - DC 200 ns instruction cycle
- · Interrupt Capability
- · 8-Level Deep Hardware Stack
- · Direct, Indirect, and Relative Addressing modes

#### **Special Microcontroller Features:**

- · Internal and External Oscillator Options
  - Precision Internal 4 MHz oscillator factory calibrated to ±1%
  - External Oscillator support for crystals and resonators
  - 5 μs wake-up from Sleep, 3.0V, typical
- · Power-Saving Sleep mode
- Wide Operating Voltage Range 2.0V to 5.5V
- · Industrial and Extended Temperature Range
- · Low-Power Power-on Reset (POR)
- Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Brown-out Detect (BOD)
- Watchdog Timer (WDT) with Independent Oscillator for Reliable Operation
- Multiplexed MCLR/Input Pin
- · Interrupt-on-Pin Change
- · Individual Programmable Weak Pull-ups
- · Programmable Code Protection
- · High Endurance Flash/EEPROM Cell
  - 100,000 write Flash endurance
  - 1,000,000 write EEPROM endurance
  - Flash/Data EEPROM Retention: > 40 years

#### Low-Power Features:

- · Standby Current:
  - 1 nA @ 2.0V, typical
- · Operating Current:
  - 8.5 μA @ 32 kHz, 2.0V, typical
  - 100 μA @ 1 MHz, 2.0V, typical
- · Watchdog Timer Current
- 300 nA @ 2.0V, typical
- · Timer1 Oscillator Current:
  - 4 μA @ 32 kHz, 2.0V, typical


#### **Peripheral Features:**

- · 6 I/O Pins with Individual Direction Control
- · High Current Sink/Source for Direct LED Drive
- · Analog Comparator module with:
  - One analog comparator
  - Programmable on-chip comparator voltage reference (CVREF) module
  - Programmable input multiplexing from device inputs
  - Comparator output is externally accessible
- Analog-to-Digital Converter module (PIC12F675):
  - 10-bit resolution
  - Programmable 4-channel input
  - Voltage reference input
- Timer0: 8-Bit Timer/Counter with 8-Bit Programmable Prescaler
- · Enhanced Timer1:
  - 16-bit timer/counter with prescaler
  - External Gate Input mode
  - Option to use OSC1 and OSC2 in LP mode as Timer1 oscillator, if INTOSC mode selected
- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via two pins

Device	Program Memory	Data N	lemory	1/0	10-bit A/D	Comporatora	Timers
Device	Flash (words)	SRAM (bytes)	EEPROM (bytes)	1/0	I/O (ch) Comparate	Comparators	8/16-bit
PIC12F629	1024	64	128	6	_	1	1/1
PIC12F675	1024	64	128	6	4	1	1/1

<sup>\* 8-</sup>bit, 8-pin devices protected by Microchip's Low Pin Count Patent: U.S. Patent No. 5,847,450. Additional U.S. and foreign patents and applications may be issued or pending.

#### **Pin Diagrams**



#### **Table of Contents**

1.0	Device Overview	7
2.0	Memory Organization	9
3.0	GPIO Port	
4.0	Timer0 Module	29
5.0	Timer1 Module with Gate Control	32
6.0	Comparator Module	37
7.0	Analog-to-Digital Converter (A/D) Module (PIC12F675 only)	43
8.0	Data EEPROM Memory	49
9.0	Special Features of the CPU	53
10.0	Instruction Set Summary	71
11.0	Development Support	81
12.0	Electrical Specifications	85
13.0	DC and AC Characteristics Graphs and Tables	107
14.0	Packaging Information	117
Appe	endix A: Data Sheet Revision History	127
Appe	endix B: Device Differences	127
Appe	endix C: Device Migrations	128
Appe	endix D: Migrating from other PIC <sup>®</sup> Devices	128
Index	· · · · · · · · · · · · · · · · · · ·	129
On-Li	ine Support	133
Syste	ems Information and Upgrade Hot Line	133
Read	ler Response	134
	uct Identification System	135

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.

NOTES:

#### 1.0 DEVICE OVERVIEW

This document contains device specific information for the PIC12F629/675. Additional information may be found in the PIC® Mid-Range Reference Manual (DS33023), which may be obtained from your local Microchip Sales Representative or downloaded from the Microchip web site. The Reference Manual should be considered a complementary document to this Data

Sheet, and is highly recommended reading for a better understanding of the device architecture and operation of the peripheral modules.

The PIC12F629 and PIC12F675 devices are covered by this Data Sheet. They are identical, except the PIC12F675 has a 10-bit A/D converter. They come in 8-pin PDIP, SOIC, MLF-S and DFN packages. Figure 1-1 shows a block diagram of the PIC12F629/675 devices. Table 1-1 shows the pinout description.

FIGURE 1-1: PIC12F629/675 BLOCK DIAGRAM




TABLE 1-1: PIC12F629/675 PINOUT DESCRIPTION

Name	Function	Input Type	Output Type	Description
GP0/AN0/CIN+/ICSPDAT	GP0	TTL	CMOS	Bidirectional I/O w/ programmable pull-up and interrupt-on-change
	AN0	AN		A/D Channel 0 input
	CIN+	AN		Comparator input
	ICSPDAT	TTL	CMOS	Serial programming I/O
GP1/AN1/CIN-/VREF/ ICSPCLK	GP1	TTL	CMOS	Bidirectional I/O w/ programmable pull-up and interrupt-on-change
	AN1	AN		A/D Channel 1 input
	CIN-	AN		Comparator input
	VREF	AN		External voltage reference
	ICSPCLK	ST		Serial programming clock
GP2/AN2/T0CKI/INT/COUT	GP2	ST	CMOS	Bidirectional I/O w/ programmable pull-up and interrupt-on-change
	AN2	AN		A/D Channel 2 input
	T0CKI	ST		TMR0 clock input
	INT	ST		External interrupt
	COUT		CMOS	Comparator output
GP3/MCLR/VPP	GP3	TTL		Input port w/ interrupt-on-change
	MCLR	ST		Master Clear
	VPP	HV		Programming voltage
GP4/AN3/T1G/OSC2/ CLKOUT	GP4	TTL	CMOS	Bidirectional I/O w/ programmable pull-up and interrupt-on-change
	AN3	AN		A/D Channel 3 input
	T1G	ST		TMR1 gate
	OSC2		XTAL	Crystal/resonator
	CLKOUT		CMOS	Fosc/4 output
GP5/T1CKI/OSC1/CLKIN	GP5	TTL	CMOS	Bidirectional I/O w/ programmable pull-up and interrupt-on-change
	T1CKI	ST		TMR1 clock
	OSC1	XTAL		Crystal/resonator
	CLKIN	ST		External clock input/RC oscillator connection
Vss	Vss	Power		Ground reference
VDD	VDD	Power	_	Positive supply

**Legend:** Shade = PIC12F675 only


TTL = TTL input buffer, ŠT = Schmitt Trigger input buffer

#### 2.0 MEMORY ORGANIZATION

#### 2.1 Program Memory Organization

The PIC12F629/675 devices have a 13-bit program counter capable of addressing an 8K x 14 program memory space. Only the first 1K x 14 (0000h-03FFh) for the PIC12F629/675 devices is physically implemented. Accessing a location above these boundaries will cause a wrap-around within the first 1K x 14 space. The Reset vector is at 0000h and the interrupt vector is at 0004h (see Figure 2-1).

FIGURE 2-1: PROGRAM MEMORY MAP
AND STACK FOR THE
DSTEMP/675



#### 2.2 Data Memory Organization

The data memory (see Figure 2-2) is partitioned into two banks, which contain the General Purpose Registers and the Special Function Registers. The Special Function Registers are located in the first 32 locations of each bank. Register locations 20h-5Fh are General Purpose Registers, implemented as static RAM and are mapped across both banks. All other RAM is unimplemented and returns '0' when read. RP0 (STATUS<5>) is the bank select bit.

- RP0 = 0 Bank 0 is selected
- RP0 = 1 Bank 1 is selected

**Note:** The IRP and RP1 bits STATUS<7:6> are reserved and should always be maintained as '0's.

## 2.2.1 GENERAL PURPOSE REGISTER FILE

The register file is organized as 64 x 8 in the PIC12F629/675 devices. Each register is accessed, either directly or indirectly, through the File Select Register FSR (see Section 2.4 "Indirect Addressing, INDF and FSR Registers").

#### 2.2.2 SPECIAL FUNCTION REGISTERS

The Special Function Registers are registers used by the CPU and peripheral functions for controlling the desired operation of the device (see Table 2-1). These registers are static RAM.

The special registers can be classified into two sets: core and peripheral. The Special Function Registers associated with the "core" are described in this section. Those related to the operation of the peripheral features are described in the section of that peripheral feature.

FIGURE 2-2: DATA MEMORY MAP OF THE PIC12F629/675

	File Address	А	File ddress
Indirect addr. (1)	Ī	Indirect addr. (1)	80h
TMR0	00h 01h	OPTION_REG	81h
	0111 02h		82h
PCL	02H	PCL	83h
STATUS FSR	03H 04h	STATUS FSR	84h
	04n 05h		85h
GPIO	06h	TRISIO	86h
	07h		87h
	0711 08h		88h
	09h		89h
PCLATH	0Ah	PCLATH	8Ah
INTCON	0Bh	INTCON	8Bh
PIR1	0Ch	PIE1	8Ch
1 1111	0Dh	1 151	8Dh
TMR1L	0Eh	PCON	8Eh
TMR1H	0Fh	1 0011	8Fh
T1CON	10h	OSCCAL	90h
110011	11h	OGGGAL	91h
	12h		92h
	13h		93h
	14h		94h
	15h	WPU	95h
	16h	IOC	96h
	17h	100	97h
	18h		98h
CMCON	19h	VRCON	99h
OMOGIV	1Ah	EEDATA	9Ah
	1Bh	EEADR	9Bh
	1Ch	EECON1	9Ch
	1Dh	EECON2 <sup>(1)</sup>	9Dh
ADRESH <sup>(2)</sup>	1Eh	ADRESL <sup>(2)</sup>	9Eh
ADCONO <sup>(2)</sup>	1Fh	ANSEL <sup>(2)</sup>	9Fh
7.200110	20h	7111022	A0h
	2011		Aon
General			
Purpose		accesses	
Registers		20h-5Fh	
64 Bytes			
	- F		DE
	5Fh 60h		DFh
	OUII		E0h
Ponts 0	7Fh	Bank 1	FFh
Bank 0		Dailk I	
		mory locations, rea	<b>d as</b> '0'.
1: Not a physical			
2: PIC12F675 onl	у.		
<u> </u>			

TABLE 2-1: SPECIAL FUNCTION REGISTERS SUMMARY

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Page
Bank 0											
00h	INDF <sup>(1)</sup>	Addressing	this Location	uses Conte	nts of FSR to	Address Dat	a Memory			0000 0000	20,61
01h	TMR0	Timer0 Mod	ule's Registe	er						xxxx xxxx	29
02h	PCL	Program Co	unter's (PC)	Least Signifi	cant Byte					0000 0000	19
03h	STATUS	IRP <sup>(2)</sup>	RP1 <sup>(2)</sup>	RP0	TO	PD	Z	DC	С	0001 1xxx	14
04h	FSR	Indirect Data	a Memory Ac	Idress Pointe	er			•		xxxx xxxx	20
05h	GPIO	_	_	GPIO5	GPIO4	GPIO3	GPIO2	GPIO1	GPIO0	xx xxxx	21
06h	_	Unimplemen	nted			•				_	_
07h	_	Unimplemen	nted							_	_
08h	_	Unimplemen	nted							_	_
09h	_	Unimplemen	nted							_	_
0Ah	PCLATH	_	_	_	Write Buffer	for Upper 5	bits of Progra	am Counter		0 0000	19
0Bh	INTCON	GIE	PEIE	T0IE	INTE	GPIE	TOIF	INTF	GPIF	0000 0000	15
0Ch	PIR1	EEIF	ADIF	_	_	CMIF	_	_	TMR1IF	00 00	17
0Dh	_	Unimplemen	Unimplemented								
0Eh	TMR1L	Holding Reg	Holding Register for the Least Significant Byte of the 16-bit Timer1								32
0Fh	TMR1H	Holding Reg	ister for the	Most Signific	ant Byte of th	ne 16-bit Time	er1			xxxx xxxx	32
10h	T1CON	_	TMR1GE	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	-000 0000	35
11h	_	Unimplemen	nted							_	_
12h	_	Unimplemer	nted							_	_
13h	_	Unimplemer	nted							_	_
14h	_	Unimplemer	nted							_	_
15h	_	Unimplemen	nted							_	_
16h	_	Unimplemen	nted							_	_
17h	_	Unimplemen	nted							_	_
18h	_	Unimplemen	nted							_	_
19h	CMCON	_	COUT	_	CINV	CIS	CM2	CM1	CM0	-0-0 0000	38
1Ah	_	Unimplemen	nted							_	_
1Bh	_	Unimplemen	nted							_	_
1Ch	_	Unimplemen	nted							_	_
1Dh	_	Unimplemen	nted							_	_
1Eh	ADRESH <sup>(3)</sup>	Most Signific	cant 8 bits of	the Left Shif	ted A/D Resu	ult or 2 bits of	the Right SI	nifted Result		xxxx xxxx	44
1Fh	ADCON0 <sup>(3)</sup>	ADFM	VCFG	_	_	CHS1	CHS0	GO/DONE	ADON	00 0000	45,61

**Legend:** — = unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: This is not a physical register.

2: These bits are reserved and should always be maintained as '0'.

3: PIC12F675 only.

SPECIAL FUNCTION REGISTERS SUMMARY (CONTINUED) **TABLE 2-1:** 

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Page
Bank 1											
80h	INDF <sup>(1)</sup>	Addressing	this Location	uses Conter	nts of FSR to	Address Dat	a Memory			0000 0000	20,61
81h	OPTION_REG	GPPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	14,31
82h	PCL	Program Co	ounter's (PC)	Least Signifi	cant Byte					0000 0000	19
83h	STATUS	IRP <sup>(2)</sup>	RP1 <sup>(2)</sup>	RP0	TO	PD	Z	DC	С	0001 1xxx	14
84h	FSR	Indirect Dat	a Memory Ad	Idress Pointe	er				•	xxxx xxxx	20
85h	TRISIO	_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0	11 1111	21
86h	_	Unimpleme	nted							_	_
87h	_	Unimpleme	nted							_	_
88h	_	Unimpleme	nted							_	_
89h	_	Unimpleme	nted							_	_
8Ah	PCLATH	_	_	_	Write Buffer	for Upper 5	bits of Progra	am Counter		0 0000	19
8Bh	INTCON	GIE	PEIE	T0IE	INTE	GPIE	T0IF	INTF	GPIF	0000 0000	15
8Ch	PIE1	EEIE	ADIE	_	_	CMIE	_	_	TMR1IE	00 00	16
8Dh	_	Unimpleme	nted							_	_
8Eh	PCON	_	_	_	_	_	_	POR	BOD	0x	18
8Fh	_	Unimpleme	nted							_	_
90h	OSCCAL	CAL5	CAL4	CAL3	CAL2	CAL1	CAL0	_	_	1000 00	18
91h	_	Unimpleme	nted							_	_
92h	_	Unimpleme	nted							_	_
93h	_	Unimpleme	nted							_	_
94h	_	Unimpleme	nted							_	_
95h	WPU	_	_	WPU5	WPU4	_	WPU2	WPU1	WPU0	11 -111	21
96h	IOC	_	_	IOC5	IOC4	IOC3	IOC2	IOC1	IOC0	00 0000	23
97h	_	Unimpleme	nted							_	_
98h	_	Unimpleme	nted							_	_
99h	VRCON	VREN	_	VRR	_	VR3	VR2	VR1	VR0	0-0- 0000	42
9Ah	EEDATA	Data EEPR	OM Data Reg	gister						0000 0000	49
9Bh	EEADR	_	Data EEPR	OM Address	Register					-000 0000	49
9Ch	EECON1	_				WRERR	WREN	WR	RD	x000	50
9Dh	EECON2 <sup>(1)</sup>	EEPROM C	ontrol Regist	er 2							50
9Eh	ADRESL <sup>(3)</sup>	Least Signif	icant 2 bits of	f the Left Shi	fted A/D Res	ult of 8 bits o	r the Right S	hifted Result		xxxx xxxx	44
9Fh	ANSEL <sup>(3)</sup>	_	ADCS2	ADCS1	ADCS0	ANS3	ANS2	ANS1	ANS0	-000 1111	46,61

— = unimplemented locations read as '0', u = unchanged, x = unknown, q = value depends on condition, shaded = unimplemented

Note 1: This is not a physical register.
2: These bits are reserved and should always be maintained as '0'.

3: PIC12F675 only.

#### 2.2.2.1 STATUS Register

The STATUS register, shown in Register 2-1, contains:

- · the arithmetic status of the ALU
- · the Reset status
- the bank select bits for data memory (SRAM)

The STATUS register can be the destination for any instruction, like any other register. If the STATUS register is the destination for an instruction that affects the Z, DC or C bits, then the write to these three bits is disabled. These bits are set or cleared according to the device logic. Furthermore, the  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are not writable. Therefore, the result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear the upper three bits and set the Z bit. This leaves the STATUS register as 000u uluu (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect any Status bits. For other instructions not affecting any Status bits, see the "Instruction Set Summary".

- Note 1: Bits IRP and RP1 (STATUS<7:6>) are not used by the PIC12F629/675 and should be maintained as clear. Use of these bits is not recommended, since this may affect upward compatibility with future products.
  - 2: The <u>C</u> and <u>DC</u> bits operate as a Borrow and <u>Digit Borrow</u> out bit, respectively, in subtraction. See the <u>SUBLW</u> and <u>SUBWF</u> instructions for examples.

#### REGISTER 2-1: STATUS: STATUS REGISTER (ADDRESS: 03h OR 83h)

Reserved	Reserved	R/W-0	R-1	R-1	R/W-x	R/W-x	R/W-x
IRP	RP1	RP0	TO	PD	Z	DC	С
bit 7							bit 0

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

bit 7	IRP: This bit is reserved and should be maintained as '0'
bit 6	RP1: This bit is reserved and should be maintained as '0'
bit 5	RP0: Register Bank Select bit (used for direct addressing) 0 = Bank 0 (00h - 7Fh) 1 = Bank 1 (80h - FFh)
bit 4	TO: Time-out bit
	<ul><li>1 = After power-up, CLRWDT instruction, or SLEEP instruction</li><li>0 = A WDT Time-out occurred</li></ul>
bit 3	PD: Power-down bit
	<ul><li>1 = After power-up or by the CLRWDT instruction</li><li>0 = By execution of the SLEEP instruction</li></ul>
bit 2	<b>Z</b> : Zero bit
	<ul><li>1 = The result of an arithmetic or logic operation is zero</li><li>0 = The result of an arithmetic or logic operation is not zero</li></ul>
bit 1	<b>DC</b> : Digit carry/borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions) For borrow, the polarity is reversed.
	<ul> <li>1 = A carry-out from the 4th low order bit of the result occurred</li> <li>0 = No carry-out from the 4th low order bit of the result</li> </ul>
bit 0	C: Carry/borrow bit (ADDWF, ADDLW, SUBLW, SUBWF instructions)
	1 = A carry-out from the Most Significant bit of the result occurred 0 = No carry-out from the Most Significant bit of the result occurred

For borrow the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low order bit of the source register.

Note:

#### 2.2.2.2 OPTION Register

The OPTION register is a readable and writable register, which contains various control bits to configure:

- TMR0/WDT prescaler
- External GP2/INT interrupt
- TMR0
- · Weak pull-ups on GPIO

Note: To achieve a 1:1 prescaler assignment for TMR0, assign the prescaler to the WDT by setting PSA bit to '1' (OPTION<3>). See Section 4.4 "Prescaler".

#### REGISTER 2-2: OPTION\_REG: OPTION REGISTER (ADDRESS: 81h)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
GPPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit, read	d as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7 <b>GPPU:</b> GPIO Pull-up Enable bit  1 = GPIO pull-ups are disabled  0 = CPIO pull-ups are applied by individual POPT letch yell	luco
<ul><li>0 = GPIO pull-ups are enabled by individual PORT latch value</li><li>bit 6</li><li>INTEDG: Interrupt Edge Select bit</li></ul>	lues
1 = Interrupt on rising edge of GP2/INT pin 0 = Interrupt on falling edge of GP2/INT pin	
bit 5 TOCS: TMR0 Clock Source Select bit	
1 = Transition on GP2/T0CKI pin	
0 = Internal instruction cycle clock (CLKOUT)	
bit 4 T0SE: TMR0 Source Edge Select bit	
<ul><li>1 = Increment on high-to-low transition on GP2/T0CKI pin</li><li>0 = Increment on low-to-high transition on GP2/T0CKI pin</li></ul>	
bit 3 <b>PSA</b> : Prescaler Assignment bit	
<ul><li>1 = Prescaler is assigned to the WDT</li><li>0 = Prescaler is assigned to the TIMER0 module</li></ul>	
bit 2-0 <b>PS2:PS0:</b> Prescaler Rate Select bits	

Bit Value	TMR0 Rate	WDT Rate
000	1:2	1:1
001	1:4	1:2
010	1:8	1:4
011	1 : 16	1:8
100	1:32	1 : 16
101	1:64	1:32
110	1 : 128	1:64
111	1:256	1 : 128

#### 2.2.2.3 INTCON Register

Legend:

R = Readable bit

The INTCON register is a readable and writable register, which contains the various enable and flag bits for TMR0 register overflow, GPIO port change and external GP2/INT pin interrupts.

Note: Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>). User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 2-3: INTCON: INTERRUPT CONTROL REGISTER (ADDRESS: 0Bh OR 8Bh)

W = Writable bit

| R/W-0 |
|-------|-------|-------|-------|-------|-------|-------|-------|
| GIE   | PEIE  | T0IE  | INTE  | GPIE  | T0IF  | INTF  | GPIF  |
| bit 7 |       |       |       |       |       |       | bit 0 |

U = Unimplemented bit, read as '0'

				,
-n = Value	e at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown
bit 7	GIE: Globa	al Interrupt Enable bit		
	1 = Enable	s all unmasked interrupts		
	0 = Disable	es all interrupts		
bit 6	<b>PEIE:</b> Peri	pheral Interrupt Enable bit		
		s all unmasked peripheral	l interrupts	
		es all peripheral interrupts		
bit 5		0 Overflow Interrupt Enab	ole bit	
		s the TMR0 interrupt		
L:4 4		es the TMR0 interrupt	ahla hit	
bit 4		I/INT External Interrupt En		
		es the GP2/INT external ir es the GP2/INT external in	•	
bit 3		Change Interrupt Enable	•	
		es the GPIO port change i		
		es the GPIO port change		
bit 2	TOIF: TMF	0 Overflow Interrupt Flag	bit <sup>(2)</sup>	
	1 = TMR0	register has overflowed (r	must be cleared in software)	
	0 = TMR0	register did not overflow		
bit 1		/INT External Interrupt Fla	•	
		•	occurred (must be cleared in s	oftware)
		P2/INT external interrupt of		
bit 0		Change Interrupt Flag bit		
		at least one of the GP5:G of the GP5:GP0 pins have	P0 pins changed state (must	be cleared in software)
Note 1:		·	•	
MOLE 1:	100 register mit	ist aiso de enableu lo enal	ble an interrupt-on-change.	

2: T0IF bit is set when TIMER0 rolls over. TIMER0 is unchanged on Reset and should be initialized before

clearing T0IF bit.

#### 2.2.2.4 PIE1 Register

The PIE1 register contains the interrupt enable bits, as shown in Register 2-4.

**Note:** Bit PEIE (INTCON<6>) must be set to enable any peripheral interrupt.

#### REGISTER 2-4: PIE1: PERIPHERAL INTERRUPT ENABLE REGISTER 1 (ADDRESS: 8Ch)

R/W-0	R/W-0	U-0	U-0	R/W-0	U-0	U-0	R/W-0
EEIE	ADIE	_	_	CMIE	_	_	TMR1IE
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	<b>EEIE:</b> EE Write Complete Interrupt Enable bit
	<ul><li>1 = Enables the EE write complete interrupt</li><li>0 = Disables the EE write complete interrupt</li></ul>
bit 6	<b>ADIE:</b> A/D Converter Interrupt Enable bit (PIC12F675 only)
	1 = Enables the A/D converter interrupt
	0 = Disables the A/D converter interrupt
bit 5-4	Unimplemented: Read as '0'
bit 3	CMIE: Comparator Interrupt Enable bit
	1 = Enables the comparator interrupt
	0 = Disables the comparator interrupt
bit 2-1	Unimplemented: Read as '0'
bit 0	TMR1IE: TMR1 Overflow Interrupt Enable bit
	1 = Enables the TMR1 overflow interrupt
	0 = Disables the TMR1 overflow interrupt

#### 2.2.2.5 PIR1 Register

The PIR1 register contains the interrupt flag bits, as shown in Register 2-5.

Interrupt flag bits are set when an interrupt condition occurs, regardless of the state of its corresponding enable bit or the global enable bit, GIE (INTCON<7>). User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt.

#### REGISTER 2-5: PIR1: PERIPHERAL INTERRUPT REGISTER 1 (ADDRESS: 0Ch)

R/W-0	R/W-0	U-0	U-0	R/W-0	U-0	U-0	R/W-0
EEIF	ADIF	_	_	CMIF	_	_	TMR1IF
bit 7							bit 0

Note:

Legend:						
R = Readable bit -n = Value at POR		W = Writable bit	U = Unimplemented bit	read as '0'		
		'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		
bit 7 <b>EEIF</b> : EEPROM Write Operation Interrupt Flag bit						
1 = The write operation completed (must be cleared in software)						

bit 6 **ADIF:** A/D Converter Interrupt Flag bit (PIC12F675 only)

1 = The A/D conversion is complete (must be cleared in software)

1 - The A/D conversion is not complete

0 = The write operation has not completed or has not been started

0 = The A/D conversion is not complete

bit 5-4 **Unimplemented:** Read as '0' bit 3 **CMIF:** Comparator Interrupt Flag bit

1 = Comparator input has changed (must be cleared in software)

0 = Comparator input has not changed

bit 2-1 **Unimplemented:** Read as '0'

bit 0 TMR1IF: TMR1 Overflow Interrupt Flag bit

1 = TMR1 register overflowed (must be cleared in software)

0 = TMR1 register did not overflow

#### 2.2.2.6 PCON Register

The Power Control (PCON) register contains flag bits to differentiate between a:

- · Power-on Reset (POR)
- · Brown-out Detect (BOD)
- · Watchdog Timer Reset (WDT)
- External MCLR Reset

The PCON Register bits are shown in Register 2-6.

#### REGISTER 2-6: PCON: POWER CONTROL REGISTER (ADDRESS: 8Eh)

U-0	U-0	U-0	U-0	U-0	U-0	R/W-0	R/W-x
_	_	_	_	_	_	POR	BOD
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-2 **Unimplemented:** Read as '0' bit 1 **POR:** Power-on Reset Status bit

1 = No Power-on Reset occurred

0 = A Power-on Reset occurred (must be set in software after a Power-on Reset occurs)

bit 0 **BOD:** Brown-out Detect Status bit

1 = No Brown-out Detect occurred

0 = A Brown-out Detect occurred (must be set in software after a Brown-out Detect occurs)

#### 2.2.2.7 OSCCAL Register

The Oscillator Calibration register (OSCCAL) is used to calibrate the internal 4 MHz oscillator. It contains 6 bits to adjust the frequency up or down to achieve 4 MHz.

The OSCCAL register bits are shown in Register 2-7.

#### REGISTER 2-7: OSCCAL: OSCILLATOR CALIBRATION REGISTER (ADDRESS: 90h)

R/W-1	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	U-0
CAL5	CAL4	CAL3	CAL2	CAL1	CAL0		_
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-2 CAL5:CAL0: 6-bit Signed Oscillator Calibration bits

111111 = Maximum frequency 100000 = Center frequency


000000 = Minimum frequency

bit 1-0 **Unimplemented:** Read as '0'

#### 2.3 PCL and PCLATH

The Program Counter (PC) is 13-bits wide. The low byte comes from the PCL register, which is a readable and writable register. The high byte (PC<12:8>) is not directly readable or writable and comes from PCLATH. On any Reset, the PC is cleared. Figure 2-3 shows the two situations for the loading of the PC. The upper example in Figure 2-3 shows how the PC is loaded on a write to PCL (PCLATH<4:0>  $\rightarrow$  PCH). The lower example in Figure 2-3 shows how the PC is loaded during a CALL or GOTO instruction (PCLATH<4:3>  $\rightarrow$  PCH).

FIGURE 2-3: LOADING OF PC IN DIFFERENT SITUATIONS



#### 2.3.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the PC (ADDWF PCL). When performing a table read using a computed GOTO method, care should be exercised if the table location crosses a PCL memory boundary (each 256-byte block). Refer to the Application Note, "Implementing a Table Read" (AN556).

#### 2.3.2 STACK

The PIC12F629/675 family has an 8-level deep x 13-bit wide hardware stack (see Figure 2-1). The stack space is not part of either program or data space and the Stack Pointer is not readable or writable. The PC is PUSHed onto the stack when a CALL instruction is executed, or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not affected by a PUSH or POP operation.

The stack operates as a circular buffer. This means that after the stack has been PUSHed eight times, the ninth push overwrites the value that was stored from the first push. The tenth push overwrites the second push (and so on).

- **Note 1:** There are no Status bits to indicate Stack Overflow or Stack Underflow conditions.
  - 2: There are no instructions/mnemonics called PUSH or POP. These are actions that occur from the execution of the CALL, RETURN, RETLW and RETFIE instructions, or the vectoring to an interrupt address.

# 2.4 Indirect Addressing, INDF and FSR Registers

The INDF register is not a physical register. Addressing the INDF register will cause indirect addressing.


Indirect addressing is possible by using the INDF register. Any instruction using the INDF register actually accesses data pointed to by the File Select Register (FSR). Reading INDF itself indirectly will produce 00h. Writing to the INDF register indirectly results in a no operation (although Status bits may be affected). An effective 9-bit address is obtained by concatenating the 8-bit FSR register and the IRP bit (STATUS<7>), as shown in Figure 2-2.

A simple program to clear RAM location 20h-2Fh using indirect addressing is shown in Example 2-1.

#### **EXAMPLE 2-1: INDIRECT ADDRESSING**

	MOVLW	0x20	;initialize pointer
	MOVWF	FSR	;to RAM
NEXT	CLRF	INDF	;clear INDF register
	INCF	FSR	;inc pointer
	BTFSS	FSR,4	;all done?
	GOTO	NEXT	;no clear next
CONTINUE			;yes continue

FIGURE 2-2: DIRECT/INDIRECT ADDRESSING PIC12F629/675



#### 3.0 GPIO PORT

There are as many as six general purpose I/O pins available. Depending on which peripherals are enabled, some or all of the pins may not be available as general purpose I/O. In general, when a peripheral is enabled, the associated pin may not be used as a general purpose I/O pin.

**Note:** Additional information on I/O ports may be found in the PIC<sup>®</sup> Mid-Range Reference Manual, (DS33023).

#### 3.1 GPIO and the TRISIO Registers

GPIO is an 6-bit wide, bidirectional port. The corresponding data direction register is TRISIO. Setting a TRISIO bit (= 1) will make the corresponding GPIO pin an input (i.e., put the corresponding output driver in a High-Impedance mode). Clearing a TRISIO bit (= 0) will make the corresponding GPIO pin an output (i.e., put the contents of the output latch on the selected pin). The exception is GP3, which is input-only and its TRISIO bit will always read as '1'. Example 3-1 shows how to initialize GPIO.

Reading the GPIO register reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are read-modify-write operations. Therefore, a write to a port implies that the port pins are read, this value is modified, and then written to the PORT data latch. GP3 reads '0' when MCLREN = 1.

The TRISIO register controls the direction of the GP pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISIO

register are maintained set when using them as analog inputs. I/O pins configured as analog inputs always read '0'.

Note: The ANSEL (9Fh) and CMCON (19h) registers (9Fh) must be initialized to configure an analog channel as a digital input. Pins configured as analog inputs will read '0'. The ANSEL register is defined for the PIC12F675.

#### **EXAMPLE 3-1: INITIALIZING GPIO**

BCF	STATUS, RP0	;Bank 0
CLRF	GPIO	;Init GPIO
MOVLW	07h	;Set GP<2:0> to
MOVWF	CMCON	;digital IO
BSF	STATUS, RPO	;Bank 1
CLRF	ANSEL	;Digital I/O
MOVLW	0Ch	;Set GP<3:2> as inputs
MOVWF	TRISIO	;and set GP<5:4,1:0>
		;as outputs
I		

#### 3.2 Additional Pin Functions

Every GPIO pin on the PIC12F629/675 has an interrupt-on-change option and every GPIO pin, except GP3, has a weak pull-up option. The next two sections describe these functions.

#### 3.2.1 WEAK PULL-UP

Each of the GPIO pins, except GP3, has an individually configurable weak internal pull-up. Control bits WPUx enable or disable each pull-up. Refer to Register 3-3. Each weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset by the GPPU bit (OPTION<7>).

#### REGISTER 3-1: GPIO: GPIO REGISTER (ADDRESS: 05h)

U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x		
_	_	GPIO5	GPIO4	GPIO3	GPIO2	GPIO1	GPIO0		
bit 7									

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-6 **Unimplemented**: Read as '0'

bit 5-0 **GPIO<5:0>**: General Purpose I/O pin

1 = Port pin is >VIH 0 = Port pin is <VIL

#### **REGISTER 3-2:** TRISIO: GPIO TRI-STATE REGISTER (ADDRESS: 85h)

U-0	-0 U-0 R/W-1		R/W-1	R-1	R/W-1	R/W-1	R/W-1
_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-6 Unimplemented: Read as '0'

bit 5-0 TRISIO<5:0>: General Purpose I/O Tri-State Control bit

1 = GPIO pin configured as an input (tri-stated)

0 = GPIO pin configured as an output

Note: TRISIO<3> always reads '1'.

#### **REGISTER 3-3:** WPU: WEAK PULL-UP REGISTER (ADDRESS: 95h)

U-0	U-0	R/W-1	R/W-1	U-0	R/W-1	R/W-1	R/W-1
_	_	WPU5	WPU4	_	WPU2	WPU1	WPU0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

'0' = Bit is cleared -n = Value at POR '1' = Bit is set x = Bit is unknown

bit 7-6 Unimplemented: Read as '0'

bit 5-4 WPU<5:4>: Weak Pull-up Register bit

> 1 = Pull-up enabled 0 = Pull-up disabled

bit 3 Unimplemented: Read as '0'

bit 2-0 WPU<2:0>: Weak Pull-up Register bit

1 = Pull-up enabled

0 = Pull-up disabled

**Note 1:** Global GPPU must be enabled for individual pull-ups to be enabled.

The weak pull-up device is automatically disabled if the pin is in Output mode (TRISIO = 0).

#### 3.2.2 INTERRUPT-ON-CHANGE

Each of the GPIO pins is individually configurable as an interrupt-on-change pin. Control bits IOC enable or disable the interrupt function for each pin. Refer to Register 3-4. The interrupt-on-change is disabled on a Power-on Reset.

For enabled interrupt-on-change pins, the values are compared with the old value latched on the last read of GPIO. The 'mismatch' outputs of the last read are OR'd together to set, the GP Port Change Interrupt flag bit (GPIF) in the INTCON register.

This interrupt can wake the device from Sleep. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of GPIO. This will end the mismatch condition.
- b) Clear the flag bit GPIF.

A mismatch condition will continue to set flag bit GPIF. Reading GPIO will end the mismatch condition and allow flag bit GPIF to be cleared.

**Note:** If a change on the I/O pin should occur when the read operation is being executed (start of the Q2 cycle), then the GPIF interrupt flag may not get set.

#### REGISTER 3-4: IOC: INTERRUPT-ON-CHANGE GPIO REGISTER (ADDRESS: 96h)

U-0 U-0		R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
_	_	IOC5 IOC4		IOC3	IOC2	IOC1	IOC0	
bit 7								

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-6 **Unimplemented**: Read as '0'

bit 5-0 IOC<5:0>: Interrupt-on-Change GPIO Control bits

1 = Interrupt-on-change enabled

0 = Interrupt-on-change disabled

Note 1: Global Interrupt Enable (GIE) must be enabled for individual interrupts to be recognized.

#### 3.3 Pin Descriptions and Diagrams

Each GPIO pin is multiplexed with other functions. The pins and their combined functions are briefly described here. For specific information about individual functions such as the comparator or the A/D, refer to the appropriate section in this Data Sheet.

#### 3.3.1 GP0/AN0/CIN+

Figure 3-1 shows the diagram for this pin. The GP0 pin is configurable to function as one of the following:


- · a general purpose I/O
- an analog input for the A/D (PIC12F675 only)
- · an analog input to the comparator

#### 3.3.2 GP1/AN1/CIN-/VREF

Figure 3-1 shows the diagram for this pin. The GP1 pin is configurable to function as one of the following:

- · as a general purpose I/O
- an analog input for the A/D (PIC12F675 only)
- · an analog input to the comparator
- a voltage reference input for the A/D (PIC12F675 only)

# FIGURE 3-1: BLOCK DIAGRAM OF GP0 AND GP1 PINS




#### 3.3.3 GP2/AN2/T0CKI/INT/COUT

Figure 3-2 shows the diagram for this pin. The GP2 pin is configurable to function as one of the following:

- a general purpose I/O
- an analog input for the A/D (PIC12F675 only)
- the clock input for TMR0
- · an external edge triggered interrupt
- · a digital output from the comparator

#### FIGURE 3-2: BLOCK DIAGRAM OF GP2




#### 3.3.4 GP3/MCLR/VPP

Figure 3-3 shows the diagram for this pin. The GP3 pin is configurable to function as one of the following:

- · a general purpose input
- · as Master Clear Reset

FIGURE 3-3: BLOCK DIAGRAM OF GP3




#### 3.3.5 GP4/AN3/T1G/OSC2/CLKOUT

Figure 3-4 shows the diagram for this pin. The GP4 pin is configurable to function as one of the following:

- · a general purpose I/O
- an analog input for the A/D (PIC12F675 only)
- · a TMR1 gate input
- · a crystal/resonator connection
- · a clock output

#### FIGURE 3-4: BLOCK DIAGRAM OF GP4



#### 3.3.6 GP5/T1CKI/OSC1/CLKIN

Figure 3-5 shows the diagram for this pin. The GP5 pin is configurable to function as one of the following:

- · a general purpose I/O
- · a TMR1 clock input
- · a crystal/resonator connection
- · a clock input

#### FIGURE 3-5: BLOCK DIAGRAM OF GP5




TABLE 3-2: SUMMARY OF REGISTERS ASSOCIATED WITH GPIO

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
05h	GPIO	_	_	GP5	GP4	GP3	GP2	GP1	GP0	xx xxxx	uu uuuu
0Bh/8Bh	INTCON	GIE	PEIE	TOIE	INTE	GPIE	TOIF	INTF	GPIF	0000 0000	0000 000u
19h	CMCON	_	COUT	_	CINV	CIS	CM2	CM1	CM0	-0-0 0000	-0-0 0000
81h	OPTION_REG	GPPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111
85h	TRISIO	_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0	11 1111	11 1111
95h	WPU	_	_	WPU5	WPU4	_	WPU2	WPU1	WPU0	11 -111	11 -111
96h	IOC	-	_	IOC5	IOC4	IOC3	IOC2	IOC1	IOC0	00 0000	00 0000
9Fh	ANSEL		ADCS2	ADCS1	ADCS0	ANS3	ANS2	ANS1	ANS0	-000 1111	-000 1111

**Legend:** x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by GPIO.

NOTES:

#### 4.0 TIMERO MODULE

The Timer0 module timer/counter has the following features:

- · 8-bit timer/counter
- · Readable and writable
- 8-bit software programmable prescaler
- · Internal or external clock select
- · Interrupt on overflow from FFh to 00h
- · Edge select for external clock

Figure 4-1 is a block diagram of the Timer0 module and the prescaler shared with the WDT.

**Note:** Additional information on the Timer0 module is available in the PIC® Mid-Range Reference Manual, (DS33023).

#### 4.1 Timer0 Operation

Timer mode is selected by clearing the TOCS bit (OPTION\_REG<5>). In Timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If TMR0 is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0 register.


Counter mode is selected by setting the T0CS bit (OPTION\_REG<5>). In this mode, the Timer0 module will increment either on every rising or falling edge of pin GP2/T0CKI. The incrementing edge is determined by the source edge (T0SE) control bit (OPTION\_REG<4>). Clearing the T0SE bit selects the rising edge.

Note: Counter mode has specific external clock requirements. Additional information on these requirements is available in the PIC® Mid-Range Reference Manual, (DS33023).

#### 4.2 Timer0 Interrupt

A Timer0 interrupt is generated when the TMR0 register timer/counter overflows from FFh to 00h. This overflow sets the T0IF bit. The interrupt can be masked by clearing the T0IE bit (INTCON<5>). The T0IF bit (INTCON<2>) must be cleared in software by the Timer0 module Interrupt Service Routine before reenabling this interrupt. The Timer0 interrupt cannot wake the processor from Sleep since the timer is shutoff during Sleep.

#### FIGURE 4-1: BLOCK DIAGRAM OF THE TIMERO/WDT PRESCALER



# 4.3 Using Timer0 with an External Clock

When no prescaler is used, the external clock input is the same as the prescaler output. The synchronization of T0CKI, with the internal phase clocks, is accomplished by sampling the prescaler output on the Q2 and Q4 cycles of the internal phase clocks. Therefore, it is necessary for T0CKI to be high for at least 2Tosc (and

a small RC delay of 20 ns) and low for at least 2Tosc (and a small RC delay of 20 ns). Refer to the electrical specification of the desired device.

Note: The ANSEL (9Fh) and CMCON (19h) registers must be initialized to configure an analog channel as a digital input. Pins configured as analog inputs will read '0'. The ANSEL register is defined for the PIC12F675.

#### REGISTER 4-1: OPTION\_REG: OPTION REGISTER (ADDRESS: 81h)

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	
GPPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	
bit 7								

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7	GPPU: GPIO Pull-up Enable bit  1 = GPIO pull-ups are disabled
bit 6	<ul> <li>0 = GPIO pull-ups are enabled by individual PORT latch values</li> <li>INTEDG: Interrupt Edge Select bit</li> <li>1 = Interrupt on rising edge of GP2/INT pin</li> <li>0 = Interrupt on falling edge of GP2/INT pin</li> </ul>
bit 5	TOCS: TMR0 Clock Source Select bit  1 = Transition on GP2/T0CK pin  0 = Internal instruction cycle clock (CLKOUT)
bit 4	<b>T0SE:</b> TMR0 Source Edge Select bit  1 = Increment on high-to-low transition on GP2/T0CKI pin  0 = Increment on low-to-high transition on GP2/T0CKI pin
bit 3	PSA: Prescaler Assignment bit  1 = Prescaler is assigned to the WDT  0 = Prescaler is assigned to the TIMER0 module
bit 2-0	PS2:PS0: Prescaler Rate Select bits  Bit Value TMR0 Rate WDT Rate

Bit Value	TMR0 Rate	WDT Rate
000	1:2	1:1
001	1:4	1:2
010	1:8	1:4
011	1 : 16	1:8
100	1:32	1 : 16
101	1:64	1:32
110	1:128	1:64
111	1:256	1 : 128

#### 4.4 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module, or as a postscaler for the Watchdog Timer. For simplicity, this counter will be referred to as "prescaler" throughout this Data Sheet. The prescaler assignment is controlled in software by the control bit PSA (OPTION\_REG<3>). Clearing the PSA bit will assign the prescaler to Timer0. Prescale values are selectable via the PS2:PS0 bits (OPTION\_REG<2:0>).

The prescaler is not readable or writable. When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF 1, MOVWF 1, BSF 1, x....etc.) will clear the prescaler. When assigned to WDT, a CLRWDT instruction will clear the prescaler along with the Watchdog Timer.

## 4.4.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control (i.e., it can be changed "on the fly" during program execution). To avoid an unintended device Reset, the following instruction sequence (Example 4-1) must be executed when changing the prescaler assignment from Timer0 to WDT.

EXAMPLE 4-1: CHANGING PRESCALER (TIMER0→WDT)

BCF CLRWDT	STATUS, RPO	;Bank 0 ;Clear WDT
CLRF	TMR0	;Clear TMR0 and ; prescaler
BSF	STATUS, RPO	;Bank 1
MOVLW MOVWF	b'00101111' OPTION REG	,
CLRWDT	OFIION_REG	; 000 or 001
MOVLW MOVWF BCF	b'00101xxx' OPTION_REG STATUS,RP0	;Set postscaler to ; desired WDT rate

To change prescaler from the WDT to the TMR0 module, use the sequence shown in Example 4-2. This precaution must be taken even if the WDT is disabled.

# EXAMPLE 4-2: CHANGING PRESCALER (WDT→TIMER0)

CLRWDT		;Clear WDT and
BSF	STATUS, RPO	; postscaler ;Bank 1
MOVLW	b'xxxx0xxx'	;Select TMR0, ; prescale, and
		; clock source
MOVWF	OPTION_REG	;
BCF	STATUS, RP0	;Bank 0

TABLE 4-1: REGISTERS ASSOCIATED WITH TIMERO

TABLE 4 II REGISTERS ASSOCIATED WITH THEE INC.											
Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
01h	TMR0	Timer0 M	odule Reg	ister						xxxx xxxx	uuuu uuuu
0Bh/8Bh	INTCON	GIE	PEIE	TOIE	INTE	GPIE	TOIF	INTF	GPIF	0000 0000	0000 000u
81h	OPTION_REG	GPPU	INTEDG	T0CS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111
85h	TRISIO	_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0	11 1111	11 1111

**Legend:** — = Unimplemented locations, read as '0', u = unchanged, x = unknown. Shaded cells are not used by the Timer0 module.

# 5.0 TIMER1 MODULE WITH GATE CONTROL


The PIC12F629/675 devices have a 16-bit timer. Figure 5-1 shows the basic block diagram of the Timer1 module. Timer1 has the following features:

- 16-bit timer/counter (TMR1H:TMR1L)
- · Readable and writable
- · Internal or external clock selection
- · Synchronous or asynchronous operation
- · Interrupt on overflow from FFFFh to 0000h
- Wake-up upon overflow (Asynchronous mode)
- Optional external enable input (T1G)
- · Optional LP oscillator

The Timer1 Control register (T1CON), shown in Register 5.1, is used to enable/disable Timer1 and select the various features of the Timer1 module.

**Note:** Additional information on timer modules is available in the PIC® Mid-Range Reference Manual, (DS33023).

FIGURE 5-1: TIMER1 BLOCK DIAGRAM



#### 5.1 Timer1 Modes of Operation

Timer1 can operate in one of three modes:

- · 16-bit timer with prescaler
- · 16-bit synchronous counter
- · 16-bit asynchronous counter

In Timer mode, Timer1 is incremented on every instruction cycle. In Counter mode, Timer1 is incremented on the rising edge of the external clock input T1CKI. In addition, the Counter mode clock can be synchronized to the microcontroller system clock or run asynchronously.

In counter and timer modules, the counter/timer clock can be gated by the  $\overline{\text{T1G}}$  input.

If an external clock oscillator is needed (and the microcontroller is using the INTOSC w/o CLKOUT), Timer1 can use the LP oscillator as a clock source.

**Note:** In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge.

#### 5.2 Timer1 Interrupt

The Timer1 register pair (TMR1H:TMR1L) increments to FFFFh and rolls over to 0000h. When Timer1 rolls over, the Timer1 interrupt flag bit (PIR1<0>) is set. To enable the interrupt on rollover, you must set these bits:

- Timer1 interrupt Enable bit (PIE1<0>)
- PEIE bit (INTCON<6>)
- GIE bit (INTCON<7>).


The interrupt is cleared by clearing the TMR1IF in the Interrupt Service Routine.

**Note:** The TMR1H:TTMR1L register pair and the TMR1IF bit should be cleared before enabling interrupts.

#### 5.3 Timer1 Prescaler

Timer1 has four prescaler options allowing 1, 2, 4, or 8 divisions of the clock input. The T1CKPS bits (T1CON<5:4>) control the prescale counter. The prescale counter is not directly readable or writable; however, the prescaler counter is cleared upon a write to TMR1H or TMR1L.

#### FIGURE 5-2: TIMER1 INCREMENTING EDGE



- Note 1: Arrows indicate counter increments.
  - 2: In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge of the clock.

#### REGISTER 5-1: T1CON: TIMER1 CONTROL REGISTER (ADDRESS: 10h)

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	TMR1GE	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7 **Unimplemented:** Read as '0'

bit 6 TMR1GE: Timer1 Gate Enable bit

If TMR1ON = 0: This bit is ignored If TMR1ON = 1:

1 = Timer1 is on if  $\overline{T1G}$  pin is low

0 = Timer1 is on

bit 5-4 T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits

11 = 1:8 Prescale Value 10 = 1:4 Prescale Value 01 = 1:2 Prescale Value 00 = 1:1 Prescale Value

bit 3 T10SCEN: LP Oscillator Enable Control bit

If INTOSC without CLKOUT oscillator is active:

1 = LP oscillator is enabled for Timer1 clock

0 = LP oscillator is off

Else:

This bit is ignored

bit 2 T1SYNC: Timer1 External Clock Input Synchronization Control bit

<u>TMR1CS = 1:</u>

1 = Do not synchronize external clock input0 = Synchronize external clock input

TMR1CS = 0:

This bit is ignored. Timer1 uses the internal clock.

bit 1 TMR1CS: Timer1 Clock Source Select bit

1 = External clock from T1OSO/T1CKI pin (on the rising edge)

0 = Internal clock (Fosc/4)

bit 0 TMR1ON: Timer1 On bit

1 = Enables Timer1
0 = Stops Timer1

#### 5.4 Timer1 Operation in Asynchronous Counter Mode

If control bit T1SYNC (T1CON<2>) is set, the external clock input is not synchronized. The timer continues to increment asynchronous to the internal phase clocks. The timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake-up the processor. However, special precautions in software are needed to read/write the timer (Section 5.4.1 "Reading and Writing Timer1 in Asynchronous Counter Mode").

Note: The ANSEL (9Fh) and CMCON (19h) registers must be initialized to configure an analog channel as a digital input. Pins configured as analog inputs will read '0'. The ANSEL register is defined for the PIC12F675.

## 5.4.1 READING AND WRITING TIMER1 IN ASYNCHRONOUS COUNTER MODE

Reading TMR1H or TMR1L, while the timer is running from an external asynchronous clock, will ensure a valid read (taken care of in hardware). However, the user should keep in mind that reading the 16-bit timer in two 8-bit values itself, poses certain problems, since the timer may overflow between the reads.

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers, while the register is incrementing. This may produce an unpredictable value in the timer register.

Reading the 16-bit value requires some care. Examples 12-2 and 12-3 in the  $PIC^{\circledR}$  Mid-Range MCU Family Reference Manual (DS33023) show how to read and write Timer1 when it is running in Asynchronous mode.

#### 5.5 Timer1 Oscillator

A crystal oscillator circuit is built-in between pins OSC1 (input) and OSC2 (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON<3>). The oscillator is a low-power oscillator rated up to 37 kHz. It will continue to run during Sleep. It is primarily intended for a 32 kHz crystal. Table 9-2 shows the capacitor selection for the Timer1 oscillator.

The Timer1 oscillator is shared with the system LP oscillator. Thus, Timer1 can use this mode only when the system clock is derived from the internal oscillator. As with the system LP oscillator, the user must provide a software time delay to ensure proper oscillator start-up.

While enabled, TRISIO4 and TRISIO5 are set. GP4 and GP5 read '0' and TRISIO4 and TRISIO5 are read '1'.

Note: The oscillator requires a start-up and stabilization time before use. Thus, T1OSCEN should be set and a suitable delay observed prior to enabling Timer1.

#### 5.6 Timer1 Operation During Sleep

Timer1 can only operate during Sleep when setup in Asynchronous Counter mode. In this mode, an external crystal or clock source can be used to increment the counter. To setup the timer to wake the device:

- Timer1 must be on (T1CON<0>)
- TMR1IE bit (PIE1<0>) must be set
- PEIE bit (INTCON<6>) must be set

The device will wake-up on an overflow. If the GIE bit (INTCON<7>) is set, the device will wake-up and jump to the Interrupt Service Routine on an overflow.

TABLE 5-1: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
0Bh/8Bh	INTCON	GIE	PEIE	TOIE	INTE	GPIE	T0IF	INTF	GPIF	0000 0000	0000 000u
0Ch	PIR1	EEIF	ADIF	-	_	CMIF	_	_	TMR1IF	00 00	00 00
0Eh	TMR1L	Holding Register for the Least Significant Byte of the 16-bit TMR1 Register								xxxx xxxx	uuuu uuuu
0Fh	TMR1H	Holding Register for the Most Significant Byte of the 16-bit TMR1 Register								xxxx xxxx	uuuu uuuu
10h	T1CON	_	TMR1GE	T1CKPS1	T1CKPS0	T10SCEN	T1SYNC	TMR1CS	TMR10N	-000 0000	-uuu uuuu
8Ch	PIE1	EEIE	ADIE	_	_	CMIE	_	_	TMR1IE	00 00	00 00

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

NOTES:

## 6.0 COMPARATOR MODULE

The PIC12F629/675 devices have one analog comparator. The inputs to the comparator are multiplexed with the GP0 and GP1 pins. There is an on-chip Comparator Voltage Reference that can also be applied to an input of the comparator. In addition, GP2 can be configured as the comparator output.

The Comparator Control Register (CMCON), shown in Register 6-1, contains the bits to control the comparator.

REGISTER 6-1: CMCON: COMPARATOR CONTROL REGISTER (ADDRESS: 19h)

U-0	R-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
_	COUT	_	CINV	CIS	CM2	CM1	CM0
bit 7							bit 0

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit	, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

bit 7 **Unimplemented:** Read as '0' bit 6 **COUT**: Comparator Output bit

When CINV = 0: 1 = Vin+ > Vin-0 = Vin+ < Vin-When CINV = 1: 1 = Vin+ < Vin-0 = Vin+ > Vin-

bit 5 **Unimplemented**: Read as '0'

bit 4 CINV: Comparator Output Inversion bit

1 = Output inverted0 = Output not inverted

bit 3 CIS: Comparator Input Switch bit

When CM2:CM0 = 110 or 101: 1 = VIN- connects to CIN+ 0 = VIN- connects to CIN-

bit 2-0 CM2:CM0: Comparator Mode bits

Figure 6-2 shows the Comparator modes and CM2:CM0 bit settings

# 6.1 Comparator Operation

A single comparator is shown in Figure 6-1, along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 6-1 represent the uncertainty due to input offsets and response time.


Note:	To use	CIN+	and	CIN-	pins	as	analog
	inputs,	the a	appro	priate	bits	mι	ust be
	progran	nmed ii	n the	CMCC	N (19	h) re	egister.

The polarity of the comparator output can be inverted by setting the CINV bit (CMCON<4>). Clearing CINV results in a non-inverted output. A complete table showing the output state versus input conditions and the polarity bit is shown in Table 6-1.

TABLE 6-1: OUTPUT STATE VS. INPUT CONDITIONS

Input Conditions	CINV	COUT
VIN- > VIN+	0	0
VIN- < VIN+	0	1
VIN- > VIN+	1	1
VIN- < VIN+	1	0

FIGURE 6-1: SINGLE COMPARATOR




# 6.2 Comparator Configuration

There are eight modes of operation for the comparator. The CMCON register, shown in Register 6-1, is used to select the mode. Figure 6-2 shows the eight possible modes. The TRISIO register controls the data direction of the comparator pins for each mode. If the Comparator mode is changed, the comparator output level may not be valid for a specified period of time. Refer to the specifications in **Section 12.0 "Electrical Specifications"**.

Note: Comparator interrupts should be disabled during a Comparator mode change. Otherwise, a false interrupt may occur.

#### FIGURE 6-2: COMPARATOR I/O OPERATING MODES




# 6.3 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 6-3. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this

range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up may occur. A maximum source impedance of 10  $k\Omega$  is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.

### FIGURE 6-3: ANALOG INPUT MODE




### 6.4 Comparator Output

The comparator output, COUT, is read through the CMCON register. This bit is read-only. The comparator output may also be directly output to the GP2 pin in three of the eight possible modes, as shown in Figure 6-2. When in one of these modes, the output on GP2 is asynchronous to the internal clock. Figure 6-4 shows the comparator output block diagram.

The TRISIO<2> bit functions as an output enable/ disable for the GP2 pin while the comparator is in an Output mode.

- Note 1: When reading the GPIO register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input according to the TTL input specification.
  - 2: Analog levels on any pin that is defined as a digital input, may cause the input buffer to consume more current than is specified.

FIGURE 6-4: MODIFIED COMPARATOR OUTPUT BLOCK DIAGRAM



# 6.5 Comparator Reference

The comparator module also allows the selection of an internally generated voltage reference for one of the comparator inputs. The internal reference signal is used for four of the eight Comparator modes. The VRCON register, Register 6-2, controls the voltage reference module shown in Figure 6-5.

# 6.5.1 CONFIGURING THE VOLTAGE REFERENCE

The voltage reference can output 32 distinct voltage levels, 16 in a high range and 16 in a low range.


The following equations determine the output voltages:

VRR = 1 (low range): CVREF = (VR3:VR0 / 24) x VDD VRR = 0 (high range): CVREF = (VDD / 4) + (VR3:VR0 x VDD / 32)

# 6.5.2 VOLTAGE REFERENCE ACCURACY/ERROR

The full range of Vss to VDD cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 6-5) keep CVREF from approaching Vss or VDD. The Voltage Reference is VDD derived and therefore, the CVREF output changes with fluctuations in VDD. The tested absolute accuracy of the Comparator Voltage Reference can be found in **Section 12.0** "Electrical Specifications".

FIGURE 6-5: COMPARATOR VOLTAGE REFERENCE BLOCK DIAGRAM



### 6.6 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output is ensured to have a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (Table 12-7).

# 6.7 Operation During Sleep

Both the comparator and voltage reference, if enabled before entering Sleep mode, remain active during Sleep. This results in higher Sleep currents than shown in the power-down specifications. The additional current consumed by the comparator and the voltage reference is shown separately in the specifications. To minimize power consumption while in Sleep mode, turn off the comparator, CM2:CM0 = 111, and voltage reference, VRCON<7> = 0.

While the comparator is enabled during Sleep, an interrupt will wake-up the device. If the device wakes up from Sleep, the contents of the CMCON and VRCON registers are not affected.

#### 6.8 Effects of a Reset

A device Reset forces the CMCON and VRCON registers to their Reset states. This forces the comparator module to be in the Comparator Reset mode, CM2:CM0 = 000 and the voltage reference to its off state. Thus, all potential inputs are analog inputs with the comparator and voltage reference disabled to consume the smallest current possible.

## REGISTER 6-2: VRCON: VOLTAGE REFERENCE CONTROL REGISTER (ADDRESS: 99h)

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
VREN	_	VRR	_	VR3	VR2	VR1	VR0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7 VREN: CVREF Enable bit

1 = CVREF circuit powered on

0 = CVREF circuit powered down, no IDD drain

bit 6 **Unimplemented:** Read as '0'

bit 5 VRR: CVREF Range Selection bit

1 = Low range0 = High range

bit 4 Unimplemented: Read as '0'

bit 3-0 **VR3:VR0:** CVREF value selection  $0 \le VR$  [3:0]  $\le 15$ 

When VRR = 1: CVREF = (VR3:VR0 / 24) \* VDD

When VRR = 0: CVREF = VDD/4 + (VR3:VR0 / 32) \* VDD

## 6.9 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of the comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<6>, to determine the actual change that has occurred. The CMIF bit, PIR1<3>, is the comparator interrupt flag. This bit must be reset in software by clearing it to '0'. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

The CMIE bit (PIE1<3>) and the PEIE bit (INT-CON<6>) must be set to enable the interrupt. In addition, the GIE bit must also be set. If any of these bits are cleared, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of CMCON. This will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition, and allow flag bit CMIF to be cleared.

Note: If a change in the CMCON register (COUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR1<3>) interrupt flag may not get set.

TABLE 6-2: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
0Bh/8Bh	INTCON	GIE	PEIE	T0IE	INTE	GPIE	TOIF	INTF	GPIF	0000 0000	0000 000u
0Ch	PIR1	EEIF	ADIF	_	_	CMIF	-	_	TMR1IF	00 00	00 00
19h	CMCON	_	COUT	_	CINV	CIS	CM2	CM1	CM0	-0-0 0000	-0-0 0000
8Ch	PIE1	EEIE	ADIE	_	_	CMIE	_	_	TMR1IE	00 00	00 00
85h	TRISIO	_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0	11 1111	11 1111
99h	VRCON	VREN	_	VRR	_	VR3	VR2	VR1	VR0	0-0- 0000	0-0- 0000


**Legend:** x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the comparator module.

# 7.0 ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE (PIC12F675 ONLY)

The Analog-to-Digital converter (A/D) allows conversion of an analog input signal to a 10-bit binary representation of that signal. The PIC12F675 has four analog inputs, multiplexed into one sample and hold

circuit. The output of the sample and hold is connected to the input of the converter. The converter generates a binary result via successive approximation and stores the result in a 10-bit register. The voltage reference used in the conversion is software selectable to either VDD or a voltage applied by the VREF pin. Figure 7-1 shows the block diagram of the A/D on the PIC12F675.

FIGURE 7-1: A/D BLOCK DIAGRAM



# 7.1 A/D Configuration and Operation

There are two registers available to control the functionality of the A/D module:

- ADCON0 (Register 7-1)
- 2. ANSEL (Register 7-2)

#### 7.1.1 ANALOG PORT PINS

The ANS3:ANS0 bits (ANSEL<3:0>) and the TRISIO bits control the operation of the A/D port pins. Set the corresponding TRISIO bits to set the pin output driver to its high-impedance state. Likewise, set the corresponding ANS bit to disable the digital input buffer.

Note: Analog voltages on any pin that is defined as a digital input may cause the input buffer to conduct excess current.

### 7.1.2 CHANNEL SELECTION

There are four analog channels on the PIC12F675, AN0 through AN3. The CHS1:CHS0 bits (ADCON0<3:2>) control which channel is connected to the sample and hold circuit.

## 7.1.3 VOLTAGE REFERENCE

There are two options for the voltage reference to the A/D converter: either VDD is used, or an analog voltage applied to VREF is used. The VCFG bit (ADCON0<6>)

controls the voltage reference selection. If VCFG is set, then the voltage on the VREF pin is the reference; otherwise, VDD is the reference.

#### 7.1.4 CONVERSION CLOCK

The A/D conversion cycle requires 11 TAD. The source of the conversion clock is software selectable via the ADCS bits (ANSEL<6:4>). There are seven possible clock options:

- Fosc/2
- Fosc/4
- Fosc/8
- Fosc/16Fosc/32
- F---/04
- Fosc/64
- FRC (dedicated internal RC oscillator)

For correct conversion, the A/D conversion clock (1/TaD) must be selected to ensure a minimum TaD of 1.6  $\mu s.$  Table 7-1 shows a few TaD calculations for selected frequencies.

TABLE 7-1: TAD vs. DEVICE OPERATING FREQUENCIES

A/D Clock	Source (TAD)	Device Frequency							
Operation	ADCS2:ADCS0	20 MHz	5 MHz	4 MHz	1.25 MHz				
2 Tosc	000	100 ns <sup>(2)</sup>	400 ns <sup>(2)</sup>	500 ns <sup>(2)</sup>	1.6 μs				
4 Tosc	100	200 ns <sup>(2)</sup>	800 ns <sup>(2)</sup>	1.0 μs <sup>(2)</sup>	3.2 μs				
8 Tosc	001	400 ns <sup>(2)</sup>	1.6 μs	2.0 μs	6.4 μs				
16 Tosc	101	800 ns <sup>(2)</sup>	3.2 μs	4.0 μs	12.8 μs <sup>(3)</sup>				
32 Tosc	010	1.6 μs	6.4 μs	8.0 μs <sup>(3)</sup>	25.6 μs <sup>(3)</sup>				
64 Tosc	110	3.2 μs	12.8 μs <sup>(3)</sup>	16.0 μs <sup>(3)</sup>	51.2 μs <sup>(3)</sup>				
A/D RC	x11	2 - 6 μs <sup>(1,4)</sup>							

Legend: Shaded cells are outside of recommended range.

- **Note 1:** The A/D RC source has a typical TAD time of 4  $\mu$ s for VDD > 3.0V.
  - 2: These values violate the minimum required TAD time.
  - 3: For faster conversion times, the selection of another clock source is recommended.
  - **4:** When the device frequency is greater than 1 MHz, the A/D RC clock source is only recommended if the conversion will be performed during Sleep.

#### 7.1.5 STARTING A CONVERSION

The A/D conversion is initiated by setting the  $GO/\overline{DONE}$  bit (ADCON0<1>). When the conversion is complete, the A/D module:

- Clears the GO/DONE bit
- Sets the ADIF flag (PIR1<6>)
- · Generates an interrupt (if enabled)

If the conversion must be aborted, the GO/DONE bit can be cleared in software. The ADRESH:ADRESL registers will not be updated with the partially complete A/D conversion sample. Instead, the ADRESH:ADRESL registers will retain the value of the


previous conversion. After an aborted conversion, a 2 TAD delay is required before another acquisition can be initiated. Following the delay, an input acquisition is automatically started on the selected channel.

Note: The GO/DONE bit should not be set in the same instruction that turns on the A/D.

#### 7.1.6 CONVERSION OUTPUT

The A/D conversion can be supplied in two formats: left or right shifted. The ADFM bit (ADCON0<7>) controls the output format. Figure 7-2 shows the output formats.

FIGURE 7-2: 10-BIT A/D RESULT FORMAT



# REGISTER 7-1: ADCON0: A/D CONTROL REGISTER (ADDRESS: 1Fh)

R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
ADFM	VCFG	_	_	CHS1	CHS0	GO/DONE	ADON
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7 ADFM: A/D Result Formed Select bit

1 = Right justified0 = Left justified

bit 6 VCFG: Voltage Reference bit

1 = VREF pin 0 = VDD

bit 5-4 **Unimplemented**: Read as '0'

bit 3-2 CHS1:CHS0: Analog Channel Select bits

00 = Channel 00 (AN0) 01 = Channel 01 (AN1) 10 = Channel 02 (AN2) 11 = Channel 03 (AN3)

bit 1 GO/DONE: A/D Conversion Status bit

1 = A/D conversion cycle in progress. Setting this bit starts an A/D conversion cycle.

This bit is automatically cleared by hardware when the A/D conversion has completed.

0 = A/D conversion completed/not in progress

bit 0 ADON: A/D Conversion Status bit

1 = A/D converter module is operating

0 = A/D converter is shut-off and consumes no operating current

## REGISTER 7-2: ANSEL: ANALOG SELECT REGISTER (ADDRESS: 9Fh)

U-0	R/W-0	R/W-0	R/W-0	R/W-1	R/W-1	R/W-1	R/W-1
_	ADCS2	ADCS1	ADCS0	ANS3	ANS2	ANS1	ANS0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7 **Unimplemented:** Read as '0'

bit 6-4 ADCS<2:0>: A/D Conversion Clock Select bits

000 = Fosc/2 001 = Fosc/8 010 = Fosc/32

x11 = FRC (clock derived from a dedicated internal oscillator = 500 kHz max)

100 = Fosc/4 101 = Fosc/16 110 = Fosc/64

bit 3-0 ANS3:ANS0: Analog Select bits

(Between analog or digital function on pins AN<3:0>, respectively.)

1 = Analog input; pin is assigned as analog input<sup>(1)</sup>

0 = Digital I/O; pin is assigned to port or special function

**Note 1:** Setting a pin to an analog input automatically disables the digital input circuitry, weak pull-ups, and interrupt-on-change. The corresponding TRISIO bit must be set to Input mode in order to allow external control of the voltage on the pin.

# 7.2 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 7-3. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD), see Figure 7-3. The maximum recommended impedance for analog sources is 10 kΩ. As the impedance

is decreased, the acquisition time may be decreased. After the analog input channel is selected (changed), this acquisition must be done before the conversion can be started.

To calculate the minimum acquisition time, Equation 7-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

To calculate the minimum acquisition time, TACQ, see the PIC® Mid-Range Reference Manual (DS33023).


#### **EQUATION 7-1: ACQUISITION TIME**

Tacq = Amplifier Settling Time +
Hold Capacitor Charging Time +
Temperature Coefficient

= TAMP + Tc + TCOFF
=  $2\mu s + Tc + [(Temperature -25^{\circ}C)(0.05\mu s/^{\circ}C)]$ Tc = CHOLD (Ric + Rss + Rs) In(1/2047)
=  $-120pF (1k\Omega + 7k\Omega + 10k\Omega) In(0.0004885)$ =  $16.47\mu s$ Tacq =  $2\mu s + 16.47\mu s + [(50^{\circ}C -25^{\circ}C)(0.05\mu s/^{\circ}C)]$ =  $19.72\mu s$ 

- Note 1: The reference voltage (VREF) has no effect on the equation, since it cancels itself out.
  - 2: The charge holding capacitor (CHOLD) is not discharged after each conversion.
  - 3: The maximum recommended impedance for analog sources is 10 k $\Omega$ . This is required to meet the pin leakage specification.

#### FIGURE 7-3: ANALOG INPUT MODEL



# 7.3 A/D Operation During Sleep

The A/D converter module can operate during Sleep. This requires the A/D clock source to be set to the internal RC oscillator. When the RC clock source is selected, the A/D waits one instruction before starting the conversion. This allows the SLEEP instruction to be executed, thus eliminating much of the switching noise from the conversion. When the conversion is complete, the GO/DONE bit is cleared, and the result is loaded into the ADRESH:ADRESL registers. If the A/D interrupt is enabled, the device awakens from Sleep. If the A/D interrupt is not enabled, the A/D module is turned off, although the ADON bit remains set.

When the A/D clock source is something other than RC, a SLEEP instruction causes the present conversion to be aborted, and the A/D module is turned off. The ADON bit remains set.

#### 7.4 Effects of Reset

A device Reset forces all registers to their Reset state. Thus the A/D module is turned off and any pending conversion is aborted. The ADRESH:ADRESL registers are unchanged.

TABLE 7-2: SUMMARY OF A/D REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
05h	GPIO	_	_	GPIO5	GPIO4	GPIO3	GPIO2	GPIO1	GPIO0	xx xxxx	uu uuuu
0Bh, 8Bh	INTCON	GIE	PEIE	T0IE	INTE	GPIE	T0IF	INTF	GPIF	0000 0000	0000 000u
0Ch	PIR1	EEIF	ADIF	_	_	CMIF	_	_	TMR1IF	00 00	00 00
1Eh	ADRESH	Most Signif	icant 8 bits c	of the Left Sh	ifted A/D res	sult or 2 bits	of the Right	Shifted Re	esult	xxxx xxxx	uuuu uuuu
1Fh	ADCON0	ADFM	VCFG	_	_	CHS1	CHS0	GO	ADON	00 0000	00 0000
85h	TRISIO	_	_	TRISIO5	TRISIO4	TRISIO3	TRISIO2	TRISIO1	TRISIO0	11 1111	11 1111
8Ch	PIE1	EEIE	ADIE	_	_	CMIE	_	_	TMR1IE	00 00	00 00
9Eh	ADRESL	Least Signi	ficant 2 bits	Result	xxxx xxxx	uuuu uuuu					
9Fh	ANSEL	_	ADCS2	ADCS1	ADCS0	ANS3	ANS2	ANS1	ANS0	-000 1111	-000 1111

Legend: x = unknown, u = unchanged, - = unimplemented read as '0'. Shaded cells are not used for A/D converter module.

## 8.0 DATA EEPROM MEMORY

The EEPROM data memory is readable and writable during normal operation (full VDD range). This memory is not directly mapped in the register file space. Instead, it is indirectly addressed through the Special Function Registers. There are four SFRs used to read and write this memory:

- EECON1
- EECON2 (not a physically implemented register)
- EEDATA
- EEADR

EEDATA holds the 8-bit data for read/write, and EEADR holds the address of the EEPROM location being accessed. PIC12F629/675 devices have 128 bytes of data EEPROM with an address range from 0h to 7Fh.

The EEPROM data memory allows byte read and write. A byte write automatically erases the location and writes the new data (erase before write). The EEPROM data memory is rated for high erase/write cycles. The write time is controlled by an on-chip timer. The write time will vary with voltage and temperature as well as from chip to chip. Please refer to AC Specifications for exact limits.

When the data memory is code-protected, the CPU may continue to read and write the data EEPROM memory. The device programmer can no longer access this memory.

Additional information on the data EEPROM is available in the  $PIC^{\circledR}$  Mid-Range Reference Manual, (DS33023).

#### REGISTER 8-1: EEDAT: EEPROM DATA REGISTER (ADDRESS: 9Ah)

| R/W-0  |
|--------|--------|--------|--------|--------|--------|--------|--------|
| EEDAT7 | EEDAT6 | EEDAT5 | EEDAT4 | EEDAT3 | EEDAT2 | EEDAT1 | EEDAT0 |
| bit 7  |        |        |        |        |        |        | bit 0  |

#### Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7-0 **EEDATn**: Byte value to write to or read from data EEPROM

### REGISTER 8-2: EEADR: EEPROM ADDRESS REGISTER (ADDRESS: 9Bh)

U-0	R/W-0						
_	EADR6	EADR5	EADR4	EADR3	EADR2	EADR1	EADR0
bit 7							bit 0

Legend:

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

bit 7 **Unimplemented**: Should be set to '0'

bit 6-0 **EEADR**: Specifies one of 128 locations for EEPROM Read/Write Operation

#### 8.1 EEADR

The EEADR register can address up to a maximum of 128 bytes of data EEPROM. Only seven of the eight bits in the register (EEADR<6:0>) are required. The MSb (bit 7) is ignored.

The upper bit should always be '0' to remain upward compatible with devices that have more data EEPROM memory.

# 8.2 EECON1 and EECON2 Registers

EECON1 is the control register with four low-order bits physically implemented. The upper four bits are non-implemented and read as '0's.

Control bits RD and WR initiate read and write, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at completion

of the read or write operation. The inability to clear the WR bit in software prevents the accidental, premature termination of a write operation.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset, or a WDT Time-out Reset during normal operation. In these situations, following Reset, the user can check the WRERR bit, clear it, and rewrite the location. The data and address will be cleared, therefore, the EEDATA and EEADR registers will need to be re-initialized.

Interrupt flag bit EEIF in the PIR1 register is set when write is complete. This bit must be cleared in software.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the data EEPROM write sequence.

# REGISTER 8-3: EECON1: EEPROM CONTROL REGISTER (ADDRESS: 9Ch)

U-0	U-0	U-0	U-0	R/W-x	R/W-0	R/S-0	R/S-0
_	_	_	_	WRERR	WREN	WR	RD
bit 7							bit 0

Leaen	٦.
Legen	и.
•	

R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

### bit 7-4 **Unimplemented**: Read as '0'

bit 3 WRERR: EEPROM Error Flag bit

- 1 = A write operation is prematurely terminated (any MCLR Reset, any WDT Reset during normal operation or BOD detect)
- 0 = The write operation completed
- bit 2 WREN: EEPROM Write Enable bit
  - 1 = Allows write cycles
  - 0 = Inhibits write to the data EEPROM
- bit 1 WR: Write Control bit
  - 1 = Initiates a write cycle (The bit is cleared by hardware once write is complete. The WR bit can only be set, not cleared, in software.)
  - 0 = Write cycle to the data EEPROM is complete
- bit 0 RD: Read Control bit
  - 1 = Initiates an EEPROM read (Read takes one cycle. RD is cleared in hardware. The RD bit can only be set, not cleared, in software).
  - 0 = Does not initiate an EEPROM read

# 8.3 Reading the EEPROM Data Memory

To read a data memory location, the user must write the address to the EEADR register and then set control bit RD (EECON1<0>), as shown in Example 8-1. The data is available, in the very next cycle, in the EEDATA register. Therefore, it can be read in the next instruction. EEDATA holds this value until another read, or until it is written to by the user (during a write operation).

#### **EXAMPLE 8-1: DATA EEPROM READ**

DOE	CHAMIIC DDO	. D = = l = 1
BSF	STATUS, RPO	;Bank 1
MOVLW	CONFIG_ADDR	;
MOVWF	EEADR	;Address to read
BSF	EECON1,RD	;EE Read
MOVF	EEDATA,W	;Move data to W

# 8.4 Writing to the EEPROM Data Memory

To write an EEPROM data location, the user must first write the address to the EEADR register and the data to the EEDATA register. Then the user must follow a specific sequence to initiate the write for each byte, as shown in Example 8-2.

#### **EXAMPLE 8-2: DATA EEPROM WRITE**

	BSF	STATUS, RPO	;Bank 1
	BSF	EECON1, WREN	;Enable write
	BCF	INTCON, GIE	;Disable INTs
	MOVLW	55h	;Unlock write
ed ed	MOVWF	EECON2	;
le le	MOVLW	AAh	;
Re	MOVWF	EECON2	;
	BSF	EECON1,WR	;Start the write
	BSF	INTCON, GIE	;Enable INTS

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write AAh to EECON2, then set WR bit) for each byte. We strongly recommend that interrupts be disabled during this code segment. A cycle count is executed during the required sequence. Any number that is not equal to the required cycles to execute the required sequence will prevent the data from being written into the EEPROM.

Additionally, the WREN bit in EECON1 must be set to enable write. This mechanism prevents accidental writes to data EEPROM due to errant (unexpected) code execution (i.e., lost programs). The user should keep the WREN bit clear at all times, except when updating EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit will not affect this write cycle. The WR bit will be inhibited from being set unless the WREN bit is set.

At the completion of the write cycle, the WR bit is cleared in hardware and the EE Write Complete Interrupt Flag bit (EEIF) is set. The user can either enable this interrupt or poll this bit. The EEIF bit (PIR<7>) register must be cleared by software.

## 8.5 Write Verify

Depending on the application, good programming practice may dictate that the value written to the data EEPROM should be verified (see Example 8-3) to the desired value to be written.

### **EXAMPLE 8-3: WRITE VERIFY**

BCF	STATUS, RPO	;Bank 0
:		;Any code
BSF	STATUS, RP0	;Bank 1 READ
MOVF	EEDATA,W	;EEDATA not changed
		;from previous write
BSF	EECON1,RD	;YES, Read the
		;value written
XORWF	EEDATA,W	
BTFSS	STATUS, Z	;Is data the same
GOTO	WRITE_ERR	;No, handle error
:		;Yes, continue

### 8.5.1 USING THE DATA EEPROM

The data EEPROM is a high-endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specifications D120 or D120A. If this is not the case, an array refresh must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory.

## 8.6 Protection Against Spurious Write

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built in. On power-up, WREN is cleared. Also, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together help prevent an accidental write during:

- brown-out
- · power glitch
- software malfunction

# 8.7 Data EEPROM Operation During Code Protect

Data memory can be code protected by programming the CPD bit to '0'.

When the data memory is code protected, the CPU is able to read and write data to the data EEPROM. It is recommended to code protect the program memory when code protecting data memory. This prevents anyone from programming zeroes over the existing code (which will execute as NOPS) to reach an added routine, programmed in unused program memory, which outputs the contents of data memory. Programming unused locations to '0' will also help prevent data memory code protection from becoming breached.

TABLE 8-1: REGISTERS/BITS ASSOCIATED WITH DATA EEPROM

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR,		Value oth Res	ner
0Ch	PIR1	EEIF	ADIF	_	_	CMIF	_	_	TMR1IF	00	00	00	00
9Ah	EEDATA	EEPROM	1 Data Re	gister						0000	0000	0000	0000
9Bh	EEADR	_	EEPROM	1 Address	Register					-000	0000	-000	0000
9Ch	EECON1	_	_		_	WRERR	WREN	WR	RD		x000		q000
9Dh	EECON2 <sup>(1)</sup>	EEPROM	1 Control F	Register 2									

 $\textbf{Legend:} \ \ x = \text{unknown}, \ u = \text{unchanged}, \ - = \text{unimplemented read as '0'}, \ q = \text{value depends upon condition}.$ 

Shaded cells are not used by data EEPROM module.

Note 1: EECON2 is not a physical register.

# 9.0 SPECIAL FEATURES OF THE CPU

Certain special circuits that deal with the needs of real time applications are what sets a microcontroller apart from other processors. The PIC12F629/675 family has a host of such features intended to:

- · maximize system reliability
- minimize cost through elimination of external components
- provide power saving operating modes and offer code protection

These features are:

- · Oscillator selection
- Reset
  - Power-on Reset (POR)
  - Power-up Timer (PWRT)
  - Oscillator Start-up Timer (OST)
  - Brown-out Detect (BOD)
- · Interrupts
- · Watchdog Timer (WDT)
- Sleep
- Code protection
- ID Locations
- · In-Circuit Serial Programming

The PIC12F629/675 has a Watchdog Timer that is controlled by Configuration bits. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT), which provides a fixed delay of 72 ms (nominal) on power-up only, designed to keep the part in Reset while the power supply stabilizes. There is also circuitry to reset the device if a brown-out occurs, which can provide at least a 72 ms Reset. With these three functions on-chip, most applications need no external Reset circuitry.

The Sleep mode is designed to offer a very low current Power-down mode. The user can wake-up from Sleep through:

- External Reset
- · Watchdog Timer wake-up
- · An interrupt

Several oscillator options are also made available to allow the part to fit the application. The INTOSC option saves system cost while the LP crystal option saves power. A set of Configuration bits are used to select various options (see Register 9.2).

#### 9.1 **Configuration Bits**

The Configuration bits can be programmed (read as '0'), or left unprogrammed (read as '1') to select various device configurations, as shown in Register 9.2. These bits are mapped in program memory location 2007h.

Address 2007h is beyond the user program memory space. It belongs to the special configuration memory space (2000h-3FFFh), which can be accessed only during programming. See PIC12F629/675 Programming Specification for more information.

#### **CONFIG: CONFIGURATION WORD (ADDRESS: 2007h) REGISTER 9-1:**

R/P-1	R/P-1	U-0	U-0	U-0	R/P-1								
BG1	BG0	_	_		CPD	CP	BODEN	MCLRE	PWRTE	WDTE	F0SC2	F0SC1	F0SC0
bit 13													bit 0

Note:

Le	~	^	n	a	
ᆫᆫ	ч	u		u	

P = Programmed using ICSP™

R = Readable bit Writable bit U = Unimplemented bit, read as '0' -n = Value at POR 0 = bit is cleared 1 = bit is set x = bit is unknown

BG1:BG0: Bandgap Calibration bits for BOD and POR voltage<sup>(1)</sup> bit 13-12

00 = Lowest bandgap voltage

11 = Highest bandgap voltage

bit 11-9 Unimplemented: Read as '0' bit 8

CPD: Data Code Protection bit(2)

1 = Data memory code protection is disabled 0 = Data memory code protection is enabled

CP: Code Protection bit(3) bit 7

1 = Program Memory code protection is disabled

0 = Program Memory code protection is enabled

BODEN: Brown-out Detect Enable bit(4) bit 6

1 = ROD enabled

0 = BOD disabled

MCLRE: GP3/MCLR Pin Function Select bit(5) bit 5

1 =  $GP3/\overline{MCLR}$  pin function is  $\overline{MCLR}$ 

0 = GP3/MCLR pin function is digital I/O, MCLR internally tied to VDD

bit 4 PWRTE: Power-up Timer Enable bit

1 = PWRT disabled

0 = PWRT enabled

bit 3 WDTE: Watchdog Timer Enable bit

1 = WDT enabled

0 = WDT disabled

FOSC2:FOSC0: Oscillator Selection bits bit 2-0

111 = RC oscillator: CLKOUT function on GP4/OSC2/CLKOUT pin, RC on GP5/OSC1/CLKIN

110 = RC oscillator: I/O function on GP4/OSC2/CLKOUT pin, RC on GP5/OSC1/CLKIN

101 = INTOSC oscillator: CLKOUT function on GP4/OSC2/CLKOUT pin, I/O function on GP5/OSC1/CLKIN

100 = INTOSC oscillator: I/O function on GP4/OSC2/CLKOUT pin, I/O function on GP5/OSC1/CLKIN

011 = EC: I/O function on GP4/OSC2/CLKOUT pin, CLKIN on GP5/OSC1/CLKIN

010 = HS oscillator: High speed crystal/resonator on GP4/OSC2/CLKOUT and GP5/OSC1/CLKIN

001 = XT oscillator: Crystal/resonator on GP4/OSC2/CLKOUT and GP5/OSC1/CLKIN

000 = LP oscillator: Low-power crystal on GP4/OSC2/CLKOUT and GP5/OSC1/CLKIN

Note 1: The Bandgap Calibration bits are factory programmed and must be read and saved prior to erasing the device as specified in the PIC12F629/675 Programming Specification. These bits are reflected in an export of the Configuration Word. Microchip Development Tools maintain all Calibration bits to factory settings.

2: The entire data EEPROM will be erased when the code protection is turned off.

3: The entire program memory will be erased, including OSCCAL value, when the code protection is turned off.

Enabling Brown-out Detect does not automatically enable Power-up Timer.

When MCLR is asserted in INTOSC or RC mode, the internal clock oscillator is disabled.

# 9.2 Oscillator Configurations

### 9.2.1 OSCILLATOR TYPES

The PIC12F629/675 can be operated in eight different oscillator option modes. The user can program three Configuration bits (FOSC2 through FOSC0) to select one of these eight modes:


- LP Low-Power Crystal
- XT Crystal/Resonator
- HS High-Speed Crystal/Resonator
- RC External Resistor/Capacitor (2 modes)
- · INTOSC Internal Oscillator (2 modes)
- EC External Clock In

Note:	Additional information on oscillator config-
	urations is available in the PIC® Mid-
	Range Reference Manual, (DS33023).

# 9.2.2 CRYSTAL OSCILLATOR / CERAMIC RESONATORS

In XT, LP or HS modes a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation (see Figure 9-1). The PIC12F629/675 oscillator design requires the use of a parallel cut crystal. Use of a series cut crystal may yield a frequency outside of the crystal manufacturers specifications. When in XT, LP or HS modes, the device can have an external clock source to drive the OSC1 pin (see Figure 9-2).

FIGURE 9-1: CRYSTAL OPERATION (OR CERAMIC RESONATOR)
HS, XT OR LP OSC
CONFIGURATION



- Note 1: See Table 9-1 and Table 9-2 for recommended values of C1 and C2.
  - 2: A series resistor may be required for AT strip cut crystals.
  - 3: RF varies with the Oscillator mode selected (Approx. value =  $10 \text{ M}\Omega$ ).

FIGURE 9-2: EXTERNAL CLOCK INPUT
OPERATION (HS, XT, EC,
OR LP OSC
CONFIGURATION)




TABLE 9-1: CAPACITOR SELECTION FOR CERAMIC RESONATORS

	Ranges Characterized:							
Mode	Freq.	OSC1(C1)	OSC2(C2)					
XT	455 kHz	68-100 pF	68-100 pF					
	2.0 MHz	15-68 pF	15-68 pF					
	4.0 MHz	15-68 pF	15-68 pF					
HS	8.0 MHz	10-68 pF	10-68 pF					
	16.0 MHz	10-22 pF	10-22 pF					

Note 1: Higher capacitance increases the stability of the oscillator but also increases the start-up time. These values are for design guidance only. Since each resonator has its own characteristics, the user should consult the resonator manufacturer for appropriate values of external components.

TABLE 9-2: CAPACITOR SELECTION FOR CRYSTAL OSCILLATOR

Mode	Freq.	OSC1(C1)	OSC2(C2)
LP	32 kHz	68-100 pF	68-100 pF
XT	100 kHz	68-150 pF	150-200 pF
	2 MHz	15-30 pF	15-30 pF
	4 MHz	15-30 pF	15-30 pF
HS	8 MHz	15-30 pF	15-30 pF
	10 MHz	15-30 pF	15-30 pF
	20 MHz	15-30 pF	15-30 pF

Note 1: Higher capacitance increases the stability of the oscillator but also increases the start-up time. These values are for design guidance only. Rs may be required in HS mode as well as XT mode to avoid overdriving crystals with low drive level specification. Since each crystal has its own characteristics, the user should consult the crystal manufacturer for appropriate values of external components.

#### 9.2.3 EXTERNAL CLOCK IN

For applications where a clock is already available elsewhere, users may directly drive the PIC12F629/675 provided that this external clock source meets the AC/DC timing requirements listed in **Section 12.0 "Electrical Specifications"**. Figure 9-2 shows how an external clock circuit should be configured.

#### 9.2.4 RC OSCILLATOR


For applications where precise timing is not a requirement, the RC oscillator option is available. The operation and functionality of the RC oscillator is dependent upon a number of variables. The RC oscillator frequency is a function of:

- · Supply voltage
- Resistor (REXT) and capacitor (CEXT) values
- · Operating temperature.

The oscillator frequency will vary from unit to unit due to normal process parameter variation. The difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to account for the tolerance of the external R and C components. Figure 9-3 shows how the R/C combination is connected.

Two options are available for this Oscillator mode which allow GP4 to be used as a general purpose I/O or to output Fosc/4.

FIGURE 9-3: RC OSCILLATOR MODE



## 9.2.5 INTERNAL 4 MHz OSCILLATOR

When calibrated, the internal oscillator provides a fixed 4 MHz (nominal) system clock. See Electrical Specifications, **Section 12.0 "Electrical Specifications"**, for information on variation over voltage and temperature.

Two options are available for this Oscillator mode which allow GP4 to be used as a general purpose I/O or to output Fosc/4.

### 9.2.5.1 Calibrating the Internal Oscillator

A calibration instruction is programmed into the last location of program memory. This instruction is a RETLW XX, where the literal is the calibration value. The literal is placed in the OSCCAL register to set the calibration of the internal oscillator. Example 9-1 demonstrates how to calibrate the internal oscillator. For best operation, decouple (with capacitance) VDD and VSS as close to the device as possible.

Note: Erasing the device will also erase the preprogrammed internal calibration value for the internal oscillator. The calibration value must be saved prior to erasing part as specified in the PIC12F629/675 Programming specification. Microchip Development Tools maintain all Calibration bits to factory settings.

# EXAMPLE 9-1: CALIBRATING THE INTERNAL OSCILLATOR

BSF CALL MOVWF	STATUS, 3FFh OSCCAL	RP0	;Bank 1 ;Get the cal value ;Calibrate
BCF	STATUS,	RP0	;Bank 0

# 9.2.6 CLKOUT

The PIC12F629/675 devices can be configured to provide a clock out signal in the INTOSC and RC oscillator modes. When configured, the oscillator frequency divided by four (Fosc/4) is output on the GP4/OSC2/CLKOUT pin. Fosc/4 can be used for test purposes or to synchronize other logic.

### 9.3 Reset

The PIC12F629/675 differentiates between various kinds of Reset:

- a) Power-on Reset (POR)
- b) WDT Reset during normal operation
- c) WDT Reset during Sleep
- d) MCLR Reset during normal operation
- e) MCLR Reset during Sleep
- f) Brown-out Detect (BOD)

Some registers are not affected in any Reset condition; their status is unknown on POR and unchanged in any other Reset. Most other registers are reset to a "Reset state" on:


- · Power-on Reset
- MCLR Reset
- WDT Reset
- · WDT Reset during Sleep
- · Brown-out Detect (BOD) Reset

They are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. TO and PD bits are set or cleared differently in different Reset situations as indicated in Table 9-4. These bits are used in software to determine the nature of the Reset. See Table 9-7 for a full description of Reset states of all registers.

A simplified block diagram of the on-chip Reset Circuit is shown in Figure 9-4.

The MCLR Reset path has a noise filter to detect and ignore small pulses. See Table 12-4 in Electrical Specifications Section for pulse-width specification.

#### FIGURE 9-4: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



#### 9.3.1 MCLR


<u>PIC12</u>F629/675 devices have a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

It should be noted that a WDT Reset does not drive  $\overline{\text{MCLR}}$  pin low.

The behavior of the ESD protection on the MCLR pin has been altered from previous devices of this family. Voltages applied to the pin that exceed its specification can result in both MCLR Resets and excessive current beyond the device specification during the ESD event. For this reason, Microchip recommends that the MCLR pin no longer be tied directly to VDD. The use of an RC network, as shown in Figure 9-5, is suggested.

An internal  $\overline{\text{MCLR}}$  option is enabled by setting the  $\underline{\text{MCLR}}$ E bit in the Configuration Word. When enabled,  $\overline{\text{MCLR}}$  is internally tied to  $\underline{\text{VDD}}$ . No internal pull-up option is available for the  $\overline{\text{MCLR}}$  pin.

FIGURE 9-5: RECOMMENDED MCLR CIRCUIT



## 9.3.2 POWER-ON RESET (POR)

The on-chip POR circuit holds the chip in Reset until VDD has reached a high enough level for proper operation. To take advantage of the POR, simply tie the MCLR pin through a resistor to VDD. This will eliminate external RC components usually needed to create Power-on Reset. A maximum rise time for VDD is required. See Electrical Specifications for details (see Section 12.0 "Electrical Specifications"). If the BOD is enabled, the maximum rise time specification does not apply. The BOD circuitry will keep the device in Reset until VDD reaches VBOD (see Section 9.3.5 "Brown-Out Detect (BOD)").

**Note:** The POR circuit does not produce an internal Reset when VDD declines.

When the device starts normal operation (exits the Reset condition), device operating parameters (i.e., voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met.

For additional information, refer to Application Note AN607, "Power-up Trouble Shooting".

#### 9.3.3 POWER-UP TIMER (PWRT)

The Power-up Timer provides a fixed 72 ms (nominal) time-out on power-up only, from POR or Brown-out Detect. The Power-up Timer operates on an internal RC oscillator. The chip is kept in Reset as long as PWRT is active. The PWRT delay allows the VDD to rise to an acceptable level. A Configuration bit, PWRTE can disable (if set) or enable (if cleared or programmed) the Power-up Timer. The Power-up Timer should always be enabled when Brown-out Detect is enabled.

The Power-up Time delay will vary from chip to chip and due to:

- VDD variation
- Temperature variation
- · Process variation.

See DC parameters for details (Section 12.0 "Electrical Specifications").

# 9.3.4 OSCILLATOR START-UP TIMER (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over. This ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP and HS modes and only on Power-on Reset or wake-up from Sleep.

# 9.3.5 BROWN-OUT DETECT (BOD)


The PIC12F629/675 members have on-chip Brown-out Detect circuitry. A Configuration bit, BODEN, can disable (if clear/programmed) or enable (if set) the Brown-out Detect circuitry. If VDD falls below VBOD for greater than parameter (TBOD) in Table 12-4 (see Section 12.0 "Electrical Specifications"), the Brown-out situation will reset the device. This will occur regardless of VDD slew-rate. A Reset is not guaranteed to occur if VDD falls below VBOD for less than parameter (TBOD).

On any Reset (Power-on, Brown-out, Watchdog, etc.), the chip will remain in Reset until VDD rises above BVDD (see Figure 9-6). The Power-up Timer will now be invoked, if enabled, and will keep the chip in Reset an additional 72 ms.

**Note:** A Brown-out Detect does not enable the Power-up Timer if the PWRTE bit in the Configuration Word is set.

If VDD drops below BVDD while the Power-up Timer is running, the chip will go back into a Brown-out Detect and the Power-up Timer will be re-initialized. Once VDD rises above BVDD, the Power-up Timer will execute a 72 ms Reset.





### 9.3.6 TIME-OUT SEQUENCE

On power-up, the time-out sequence is as follows: first, PWRT time-out is invoked after POR has expired. Then, OST is activated. The total time-out will vary based on oscillator configuration and PWRTE bit status. For example, in EC mode with PWRTE bit erased (PWRT disabled), there will be no time-out at all. Figure 9-7, Figure 9-8 and Figure 9-9 depict time-out sequences.

Since the time-outs occur from the POR pulse, if MCLR is kept low long enough, the time-outs will expire. Then bringing MCLR high will begin execution immediately (see Figure 9-8). This is useful for testing purposes or to synchronize more than one PIC12F629/675 device operating in parallel.

Table 9-6 shows the Reset conditions for some special registers, while Table 9-7 shows the Reset conditions for all the registers.

# 9.3.7 POWER CONTROL (PCON) STATUS REGISTER

The power CONTROL/STATUS register, PCON (address 8Eh) has two bits.

Bit 0 is  $\overline{BOD}$  (Brown-out).  $\overline{BOD}$  is unknown on Poweron Reset. It must then be set by the user and checked on subsequent Resets to see if  $\overline{BOD} = 0$ , indicating that a brown-out has occurred. The  $\overline{BOD}$  Status bit is a "don't care" and is not necessarily predictable if the brown-out circuit is disabled (by setting  $\overline{BODEN}$  bit = 0 in the Configuration Word).

Bit 1 is POR (Power-on Reset). It is a '0' on Power-on Reset and unaffected otherwise. The user must write a '1' to this bit following a Power-on Reset. On a subsequent Reset, if POR is '0', it will indicate that a Power-on Reset must have occurred (i.e., VDD may have gone too low).

TABLE 9-3: TIME-OUT IN VARIOUS SITUATIONS

Oscillator Configuration	Powe	er-up	Brown-o	Wake-up	
Oscillator Configuration	PWRTE = 0	PWRTE = 1	PWRTE = 0	PWRTE = 1	from Sleep
XT, HS, LP	TPWRT + 1024•Tosc	1024•Tosc	TPWRT + 1024•Tosc	1024•Tosc	1024•Tosc
RC, EC, INTOSC	TPWRT	_	TPWRT	_	_

TABLE 9-4: STATUS/PCON BITS AND THEIR SIGNIFICANCE

POR	BOD	то	PD	
0	u	1	1	Power-on Reset
1	0	1	1	Brown-out Detect
u	u	0	u	WDT Reset
u	u	0	0	WDT Wake-up
u	u	u	u	MCLR Reset during normal operation
u	u	1	0	MCLR Reset during Sleep

Legend: u = unchanged, x = unknown

TABLE 9-5: SUMMARY OF REGISTERS ASSOCIATED WITH BROWN-OUT

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets <sup>(1)</sup>
03h	STATUS	IRP	RP1	RPO	TO	PD	Z	DC	С	0001 1xxx	000q quuu
8Eh	PCON	1	1	1	1	1	1	POR	BOD	0x	uq

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0', q = value depends on condition.

**Note 1:** Other (non Power-up) Resets include MCLR Reset, Brown-out Detect and Watchdog Timer Reset during normal operation.

TABLE 9-6: INITIALIZATION CONDITION FOR SPECIAL REGISTERS

Condition	Program Counter	STATUS Register	PCON Register
Power-on Reset	000h	0001 1xxx	0x
MCLR Reset during normal operation	000h	000u uuuu	uu
MCLR Reset during Sleep	000h	0001 Ouuu	uu
WDT Reset	000h	0000 uuuu	uu
WDT Wake-up	PC + 1	uuu0 0uuu	uu
Brown-out Detect	000h	0001 1uuu	10
Interrupt Wake-up from Sleep	PC + 1 <sup>(1)</sup>	uuu1 0uuu	uu

**Legend:** u = unchanged, x = unknown, - = unimplemented bit, reads as '0'.

**Note 1:** When the wake-up is due to an interrupt and global enable bit GIE is set, the PC is loaded with the interrupt vector (0004h) after execution of PC + 1.

TABLE 9-7: INITIALIZATION CONDITION FOR REGISTERS

Register	Address	Power-on Reset	MCLR Reset during normal operation     MCLR Reset during Sleep     WDT Reset     Brown-out Detect <sup>(1)</sup>	Wake-up from Sleep through interrupt     Wake-up from Sleep through WDT Time-out
W	_	xxxx xxxx	uuuu uuuu	uuuu uuuu
INDF	00h/80h	_	_	_
TMR0	01h	xxxx xxxx	uuuu uuuu	uuuu uuuu
PCL	02h/82h	0000 0000	0000 0000	PC + 1 <sup>(3)</sup>
STATUS	03h/83h	0001 1xxx	000q quuu <sup>(4)</sup>	uuuq quuu <sup>(4)</sup>
FSR	04h/84h	xxxx xxxx	uuuu uuuu	uuuu uuuu
GPIO	05h	xx xxxx	uu uuuu	uu uuuu
PCLATH	0Ah/8Ah	0 0000	0 0000	u uuuu
INTCON	0Bh/8Bh	0000 0000	0000 000u	uuuu uuqq <sup>(2)</sup>
PIR1	0Ch	00 00	00 00	qq qq <sup>(2,5)</sup>
T1CON	10h	-000 0000	-uuu uuuu	-uuu uuuu
CMCON	19h	-0-0 0000	-0-0 0000	-u-u uuuu
ADRESH	1Eh	xxxx xxxx	uuuu uuuu	uuuu uuuu
ADCON0	1Fh	00 0000	00 0000	uu uuuu
OPTION_REG	81h	1111 1111	1111 1111	uuuu uuuu
TRISIO	85h	11 1111	11 1111	uu uuuu
PIE1	8Ch	00 00	00 00	uu uu
PCON	8Eh	0x	uu <sup>(1,6)</sup>	uu
OSCCAL	90h	1000 00	1000 00	uuuu uu
WPU	95h	11 -111	11 -111	uuuu uuuu
IOC	96h	00 0000	00 0000	uu uuuu
VRCON	99h	0-0- 0000	0-0- 0000	u-u- uuuu
EEDATA	9Ah	0000 0000	0000 0000	uuuu uuuu
EEADR	9Bh	-000 0000	-000 0000	-uuu uuuu
EECON1	9Ch	x000	q000	uuuu
EECON2	9Dh			
ADRESL	9Eh	xxxx xxxx	uuuu uuuu	uuuu uuuu
ANSEL	9Fh	-000 1111	-000 1111	-uuu uuuu

 $\textbf{Legend:} \ u = \text{unchanged,} \ x = \text{unknown,} \ - = \text{unimplemented bit, reads as `0', } \ q = \text{value depends on condition.}$ 

- Note 1: If VDD goes too low, Power-on Reset will be activated and registers will be affected differently.
  - 2: One or more bits in INTCON and/or PIR1 will be affected (to cause wake-up).
  - **3:** When the wake-up is due to an interrupt and the GIE bit is set, the PC is loaded with the interrupt vector (0004h).
  - 4: See Table 9-6 for Reset value for specific condition.
  - **5:** If wake-up was due to data EEPROM write completing, Bit 7 = 1; A/D conversion completing, Bit 6 = 1; Comparator input changing, bit 3 = 1; or Timer1 rolling over, bit 0 = 1. All other interrupts generating a wake-up will cause these bits to = u.
  - **6:** If Reset was due to brown-out, then bit 0 = 0. All other Resets will cause bit 0 = u.

FIGURE 9-7: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1




FIGURE 9-8: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2





FIGURE 9-9: TIME-OUT SEQUENCE ON POWER-UP (MCLR TIED TO VDD)



# 9.4 Interrupts

The PIC12F629/675 has 7 sources of interrupt:

- · External Interrupt GP2/INT
- TMR0 Overflow Interrupt
- · GPIO Change Interrupts
- Comparator Interrupt
- A/D Interrupt (PIC12F675 only)
- TMR1 Overflow Interrupt
- · EEPROM Data Write Interrupt

The Interrupt Control register (INTCON) and Peripheral Interrupt register (PIR) record individual interrupt requests in flag bits. The INTCON register also has individual and Global Interrupt Enable (GIE) bits.

A Global Interrupt Enable bit, GIE (INTCON<7>) enables (if set) all unmasked interrupts, or disables (if cleared) all interrupts. Individual interrupts can be disabled through their corresponding enable bits in INTCON register and PIE register. GIE is cleared on Reset.

The return from interrupt instruction, RETFIE, exits interrupt routine, as well as sets the GIE bit, which re-enables unmasked interrupts.

The following interrupt flags are contained in the INTCON register:

- · INT pin interrupt
- · GP port change interrupt
- · TMR0 overflow interrupt

The peripheral interrupt flags are contained in the special register PIR1. The corresponding interrupt enable bit is contained in special register PIE1.

The following interrupt flags are contained in the PIR register:

- · EEPROM data write interrupt
- · A/D interrupt
- · Comparator interrupt
- · Timer1 overflow interrupt

When an interrupt is serviced:

- · The GIE is cleared to disable any further interrupt
- · The return address is pushed onto the stack
- The PC is loaded with 0004h

Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bit(s) must be cleared in software before re-enabling interrupts to avoid GP2/ INT recursive interrupts.

For external interrupt events, such as the INT pin, or GP port change interrupt, the interrupt latency will be three or four instruction cycles. The exact latency depends upon when the interrupt event occurs (see Figure 9-11). The latency is the same for one or two-cycle instructions. Once in the Interrupt Service Routine, the source(s) of the interrupt can be

determined by polling the interrupt flag bits. The interrupt flag bit(s) must be cleared in software before re-enabling interrupts to avoid multiple interrupt requests.

- Note 1: Individual interrupt flag bits are set, regardless of the status of their corresponding mask bit or the GIE bit.
  - 2: When an instruction that clears the GIE bit is executed, any interrupts that were pending for execution in the next cycle are ignored. The interrupts which were ignored are still pending to be serviced when the GIE bit is set again.

FIGURE 9-10: **INTERRUPT LOGIC** IOC-GP0 -IOC0 -IOC-GP1 \_ IOC1 \_ IOC-GP2 \_ IOC2 \_ IOC-GP3 -IOC3 -IOC-GP4 — IOC4 — IOC-GP5 – IOC5 – TOIF \_ Wake-up (If in Sleep mode) INTF INTE -Interrupt to CPU TMR1IF -**GPIF** GPIE CMIF \_ PEIE -ADIF -(1) GIE EEIF EEIE Note 1: PIC12F675 only.

#### 9.4.1 GP2/INT INTERRUPT

External interrupt on GP2/INT pin is edge-triggered; either rising if INTEDG bit (OPTION<6>) is set, of falling, if INTEDG bit is clear. When a valid edge appears on the GP2/INT pin, the INTF bit (INTCON<1>) is set. This interrupt can be disabled by clearing the INTE control bit (INTCON<4>). The INTF bit must be cleared in software in the Interrupt Service Routine before re-enabling this interrupt. The GP2/INT interrupt can wake-up the processor from Sleep if the INTE bit was set prior to going into Sleep. The status of the GIE bit decides whether or not the processor branches to the interrupt vector following wake-up. See Section 9.7 "Power-Down Mode (Sleep)" for details on Sleep and Figure 9-13 for timing of wake-up from Sleep through GP2/INT interrupt.

Note: The ANSEL (9Fh) and CMCON (19h) registers must be initialized to configure an analog channel as a digital input. Pins configured as analog inputs will read '0'. The ANSEL register is defined for the PIC12F675.

### 9.4.2 TMR0 INTERRUPT

An overflow (FFh  $\rightarrow$  00h) in the TMR0 register will set the T0IF (INTCON<2>) bit. The interrupt can be enabled/disabled by setting/clearing T0IE (INTCON<5>) bit. For operation of the Timer0 module, see **Section 4.0 "Timer0 Module"**.

#### 9.4.3 GPIO INTERRUPT

An input change on GPIO change sets the GPIF (INTCON<0>) bit. The interrupt can be enabled/disabled by setting/clearing the GPIE (INTCON<3>) bit. Plus individual pins can be configured through the IOC register.

Note: If a change on the I/O pin should occur when the read operation is being executed (start of the Q2 cycle), then the GPIF interrupt flag may not get set.

### 9.4.4 COMPARATOR INTERRUPT


See **Section 6.9 "Comparator Interrupts"** for description of comparator interrupt.

### 9.4.5 A/D CONVERTER INTERRUPT

After a conversion is complete, the ADIF flag (PIR<6>) is set. The interrupt can be enabled/disabled by setting or clearing ADIE (PIE<6>).

See Section 7.0 "Analog-to-Digital Converter (A/D) Module (PIC12F675 only)" for operation of the A/D converter interrupt.





Note 1: INTF flag is sampled here (every Q1).

- 2: Asynchronous interrupt latency = 3-4 Tcy. Synchronous latency = 3 Tcy, where Tcy = instruction cycle time. Latency is the same whether Inst (PC) is a single cycle or a 2-cycle instruction.
- 3: CLKOUT is available only in RC Oscillator mode.
- 4: For minimum width of INT pulse, refer to AC specs.
- 5: INTF is enabled to be set any time during the Q4-Q1 cycles.

#### TABLE 9-8: SUMMARY OF INTERRUPT REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets	
0Bh, 8Bh	INTCON	GIE	PEIE	T0IE	INTE	GPIE	T0IF	INTF	GPIF	0000 0000	0000 000u	
0Ch	PIR1	EEIF	ADIF	_	_	CMIF	_	_	TMR1IF	00 00	00 00	
8Ch	PIE1	EEIE	ADIE	_	_	CMIE	_	_	TMR1IE	00 00	00 00	

**Legend:** x = unknown, u = unchanged, - = unimplemented read as '0', <math>q = value depends upon condition. Shaded cells are not used by the interrupt module.

## 9.5 Context Saving During Interrupts

During an interrupt, only the return PC value is saved on the stack. Typically, users may wish to save key registers during an interrupt (e.g., W register and STATUS register). This must be implemented in software.

Example 9-2 stores and restores the STATUS and W registers. The user register, W\_TEMP, must be defined in both banks and must be defined at the same offset from the bank base address (i.e., W\_TEMP is defined at 0x20 in Bank 0 and it must also be defined at 0xA0 in Bank 1). The user register, STATUS\_TEMP, must be defined in Bank 0. The Example 9-2:

- · Stores the W register
- Stores the STATUS register in Bank 0
- · Executes the ISR code
- Restores the STATUS (and bank select bit register)
- Restores the W register

# EXAMPLE 9-2: SAVING THE STATUS AND W REGISTERS IN RAM

MOVWF	W_TEMP	<pre>;copy W to temp register, could be in either bank</pre>
SWAPF	STATUS, W	;swap status to be saved into W
BCF	STATUS, RPO	<pre>;change to bank 0 regardless of current bank</pre>
MOVWF	STATUS_TEMP	;save status to bank 0 register
:		
: (	ISR)	
:		
SWAPF	STATUS_TEMP,	W;swap STATUS_TEMP register into
		W, sets bank to original state
MOVWF	STATUS	;move W into STATUS register
SWAPF	W_TEMP,F	;swap W_TEMP
SWAPF	W_TEMP,W	;swap W_TEMP into W

# 9.6 Watchdog Timer (WDT)

The Watchdog Timer is a free running, on-chip RC oscillator, which requires no external components. This RC oscillator is separate from the external RC oscillator of the CLKIN pin and INTOSC. That means that the WDT will run, even if the clock on the OSC1 and OSC2 pins of the device has been stopped (for example, by execution of a SLEEP instruction). During normal operation, a WDT Time-out generates a device Reset. If the device is in Sleep mode, a WDT Time-out causes the device to wake-up and continue with normal operation. The WDT can be permanently disabled by programming the Configuration bit WDTE as clear (Section 9.1 "Configuration Bits").

## 9.6.1 WDT PERIOD

The WDT has a nominal time-out period of 18 ms, (with no prescaler). The time-out periods vary with temperature, VDD and process variations from part to part (see DC specs). If longer time-out periods are desired, a prescaler with a division ratio of up to 1:128 can be assigned to the WDT under software control by writing to the OPTION register. Thus, time-out periods up to 2.3 seconds can be realized.

The CLRWDT and SLEEP instructions clear the WDT and the prescaler, if assigned to the WDT, and prevent it from timing out and generating a device Reset.

The TO bit in the STATUS register will be cleared upon a Watchdog Timer Time-out.

# 9.6.2 WDT PROGRAMMING CONSIDERATIONS

It should also be taken in account that under worstcase conditions (i.e., VDD = Min., Temperature = Max., Max. WDT prescaler) it may take several seconds before a WDT Time-out occurs.

DS41190G-page 66

## FIGURE 9-12: WATCHDOG TIMER BLOCK DIAGRAM




TABLE 9-9: SUMMARY OF WATCHDOG TIMER REGISTERS

Address	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOD	Value on all other Resets
81h	OPTION_REG	GPPU	INTEDG	TOCS	T0SE	PSA	PS2	PS1	PS0	1111 1111	1111 1111
2007h	Config. bits	CP	BODEN	MCLRE	PWRTE	WDTE	F0SC2	F0SC1	F0SC0	uuuu uuuu	uuuu uuuu

**Legend:** u = Unchanged, shaded cells are not used by the Watchdog Timer.

## 9.7 Power-Down Mode (Sleep)

The Power-down mode is entered by executing a SLEEP instruction.

If the Watchdog Timer is enabled:

- · WDT will be cleared but keeps running
- PD bit in the STATUS register is cleared
- TO bit is set
- · Oscillator driver is turned off
- I/O ports maintain the status they had before Sleep was executed (driving high, low, or high-impedance).

For lowest current consumption in this mode, all I/O pins should be either at VDD, or Vss, with no external circuitry drawing current from the I/O pin and the comparators and CVREF should be disabled. I/O pins that are high-impedance inputs should be pulled high or low externally to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or Vss for lowest current consumption. The contribution from on-chip pull-ups on GPIO should be considered.

The MCLR pin must be at a logic high level (VIHMC).

Note: It should be noted that a Reset generated by a WDT Time-out does not drive MCLR pin low.

## 9.7.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin
- 2. Watchdog Timer Wake-up (if WDT was enabled)
- Interrupt from GP2/INT pin, GPIO change, or a peripheral interrupt.


The first event will cause a device Reset. The two latter events are considered a continuation of program execution. The  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits in the STATUS register can be used to determine the cause of device Reset. The  $\overline{\text{PD}}$  bit, which is set on power-up, is cleared when Sleep is invoked.  $\overline{\text{TO}}$  bit is cleared if WDT Wake-up occurred.

When the SLEEP instruction is being executed, the next instruction (PC + 1) is pre-fetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction, then branches to the interrupt address (0004h). In cases where the execution of the instruction following SLEEP is not desirable, the user should have an NOP after the SLEEP instruction.

Note: If the global interrupts are disabled (GIE is cleared), but any interrupt source has both its interrupt enable bit and the corresponding interrupt flag bits set, the device will immediately wake-up from Sleep. The SLEEP instruction is completely executed.

The WDT is cleared when the device wakes up from Sleep, regardless of the source of wake-up.

## FIGURE 9-13: WAKE-UP FROM SLEEP THROUGH INTERRUPT



GIE = 1 assumed. In this case after wake-up, the processor jumps to the interrupt routine. If GIE = 0, execution will continue in-line. CLKOUT is not available in XT, HS, LP or EC Osc modes, but shown here for timing reference.

### 9.8 Code Protection

If the code protection bit(s) have not been programmed, the on-chip program memory can be read out for verification purposes.

Note: The entire data EEPROM and Flash program memory will be erased when the code protection is turned off. The INTOSC calibration data is also erased. See PIC12F629/675 Programming Specification for more information.

#### 9.9 ID Locations

Four memory locations (2000h-2003h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are not accessible during normal execution but are readable and writable during Program/Verify. Only the Least Significant 7 bits of the ID locations are used.

## 9.10 In-Circuit Serial Programming

The PIC12F629/675 microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data, and three other lines for:

- power
- ground
- · programming voltage


This allows customers to manufacture boards with unprogrammed devices, and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

The device is placed into a Program/Verify mode by <a href="https://holding.nd/">holding</a> the GP0 and GP1 pins low, while raising the <a href="https://mclim.nd/">MCLR (VPP)</a> pin from VIL to VIHH (see Programming Specification). GP0 becomes the programming data and GP1 becomes the programming clock. Both GP0 and GP1 are Schmitt Trigger inputs in this mode.

After Reset, to place the device into Programming/ Verify mode, the PC is at location 00h. A 6-bit command is then supplied to the device. Depending on the command, 14-bits of program data are then supplied to or from the device, depending on whether the command was a load or a read. For complete details of serial programming, please refer to the Programming Specifications.

A typical In-Circuit Serial Programming connection is shown in Figure 9-14.

FIGURE 9-14: TYPICAL IN-CIRCUIT SERIAL PROGRAMMING



# 9.11 In-Circuit Debugger

Since in-circuit debugging requires the loss of clock, data and  $\overline{MCLR}$  pins, MPLAB  $^{\circledR}$  ICD 2 development with an 8-pin device is not practical. A special 14-pin PIC12F675-ICD device is used with MPLAB ICD 2 to provide separate clock, data and  $\overline{MCLR}$  pins and frees all normally available pins to the user.

This special ICD device is mounted on the top of the header and its signals are routed to the MPLAB ICD 2 connector. On the bottom of the header is an 8-pin socket that plugs into the user's target via the 8-pin stand-off connector.

When the  $\overline{\text{ICD}}$  pin on the PIC12F675-ICD device is held low, the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB ICD 2. When the microcontroller has this feature enabled, some of the resources are not available for general use. Table 9-10 shows which features are consumed by the background debugger:

TABLE 9-10: DEBUGGER RESOURCES

I/O pins	ICDCLK, ICDDATA
Stack	1 level
Program Memory	Address 0h must be NOP 300h-3FEh

For more information, see 8-Pin MPLAB ICD 2 Header Information Sheet (DS51292) available on Microchip's web site (www.microchip.com).

NOTES:

### 10.0 INSTRUCTION SET SUMMARY

The PIC12F629/675 instruction set is highly orthogonal and is comprised of three basic categories:

- · Byte-oriented operations
- · Bit-oriented operations
- · Literal and control operations

Each PIC12F629/675 instruction is a 14-bit word divided into an **opcode**, which specifies the instruction type, and one or more **operands**, which further specify the operation of the instruction. The formats for each of the categories is presented in Figure 10-1, while the various opcode fields are summarized in Table 10-1.

Table 10-2 lists the instructions recognized by the MPASM $^{\text{TM}}$  assembler. A complete description of each instruction is also available in the PIC $^{\textcircled{\$}}$  Mid-Range Reference Manual (DS33023).

For **byte-oriented** instructions, 'f' represents a file register designator and 'd' represents a destination designator. The file register designator specifies which file register is to be used by the instruction.

The destination designator specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the W register. If 'd' is one, the result is placed in the file register specified in the instruction.

For **bit-oriented** instructions, 'b' represents a bit field designator, which selects the bit affected by the operation, while 'f' represents the address of the file in which the bit is located.

For **literal and control** operations, 'k' represents an 8-bit or 11-bit constant, or literal value.

One instruction cycle consists of four oscillator periods; for an oscillator frequency of 4 MHz, this gives a normal instruction execution time of 1  $\mu s$ . All instructions are executed within a single instruction cycle, unless a conditional test is true, or the program counter is changed as a result of an instruction. When this occurs, the execution takes two instruction cycles, with the second cycle executed as a NOP.

Note: To maintain upward compatibility with future products, do not use the OPTION and TRISIO instructions.

All instruction examples use the format '0xhh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

## 10.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (R-M-W) operation. The register is read, the data is modified, and the result is stored according to either the instruction, or the destination designator 'd'. A read operation is performed on a register even if the instruction writes to that register.

For example, a CLRF GPIO instruction will read GPIO, clear all the data bits, then write the result back to GPIO. This example would have the unintended result that the condition that sets the GPIF flag would be cleared

TABLE 10-1: OPCODE FIELD DESCRIPTIONS

Field	Description
f	Register file address (0x00 to 0x7F)
W	Working register (accumulator)
b	Bit address within an 8-bit file register
k	Literal field, constant data or label
х	Don't care location (= 0 or 1).  The assembler will generate code with x = 0.  It is the recommended form of use for compatibility with all Microchip software tools.
d	Destination select; d = 0: store result in W, d = 1: store result in file register f. Default is d = 1.
PC	Program Counter
ТО	Time-out bit
PD	Power-down bit

# FIGURE 10-1: GENERAL FORMAT FOR INSTRUCTIONS




TABLE 10-2: PIC12F629/675 INSTRUCTION SET

Operands Description	Cycles					Status	Notes
		MSb			LSb	Affected	Notes
BYTE-ORIEN	TED FILE REGISTER OPE	RATIO	NS				
ADDWF f, d Add W and f	1	0.0	0111	dfff	ffff	C,DC,Z	1,2
ANDWF f, d AND W with f	1	0.0	0101	dfff	ffff	Z	1,2
CLRF f Clear f	1	0.0	0001	lfff	ffff	Z	2
CLRW - Clear W	1	0.0	0001	0xxx	xxxx	Z	
COMF f, d Complement f	1	0.0	1001	dfff	ffff	Z	1,2
DECF f, d Decrement f	1	0.0	0011	dfff	ffff	Z	1,2
DECFSZ f, d Decrement f, Skip if 0	1(2)	0.0	1011	dfff	ffff		1,2,3
INCF f, d Increment f	l ì	0.0	1010	dfff	ffff	Z	1,2
INCFSZ f, d Increment f, Skip if 0	1(2)	0.0	1111	dfff	ffff		1,2,3
IORWF f, d Inclusive OR W with f	l ì	0.0	0100	dfff	ffff	Z	1,2
MOVF f, d Move f	1	0.0	1000	dfff	ffff	Z	1,2
MOVWF f Move W to f	1	0.0	0000	lfff	ffff		
NOP - No Operation	1	0.0	0000	0xx0	0000		
RLF f, d Rotate Left f through Carry	1	0.0	1101	dfff	ffff	С	1,2
RRF f, d Rotate Right f through Carry	1	0.0	1100	dfff	ffff	С	1,2
SUBWF f, d Subtract W from f	1	0.0	0010	dfff	ffff	C,DC,Z	1,2
SWAPF f, d Swap nibbles in f	1 1	0.0	1110	dfff	ffff	, ,	1,2
XORWF f, d Exclusive OR W with f	1	0.0	0110	dfff	ffff	Z	1,2
BIT-ORIENT	ED FILE REGISTER OPER	RATION	NS				
BCF f, b Bit Clear f	1	01	00bb	bfff	ffff		1,2
BSF f, b Bit Set f	1	01	01bb	bfff	ffff		1,2
BTFSC f, b Bit Test f, Skip if Clear	1 (2)	01	10bb	bfff	ffff		3
BTFSS f, b Bit Test f, Skip if Set	1 (2)	01	11bb	bfff	ffff		3
LITERAL	AND CONTROL OPERAT	IONS					
ADDLW k Add literal and W	1	11	111x	kkkk	kkkk	C,DC,Z	
ANDLW k AND literal with W	1	11	1001	kkkk	kkkk	Z	
CALL k Call subroutine	2	10	0kkk	kkkk	kkkk		
CLRWDT - Clear Watchdog Timer	1	0.0	0000	0110	0100	TO,PD	
GOTO k Go to address	2	10	1kkk	kkkk	kkkk		
IORLW k Inclusive OR literal with W	1	11	1000	kkkk	kkkk	Z	
MOVLW k Move literal to W	1	11	00xx	kkkk	kkkk		
RETFIE - Return from interrupt	2	00	0000	0000	1001		
RETLW k Return with literal in W	2	11	01xx	kkkk	kkkk		
RETURN - Return from Subroutine	2	00	0000	0000	1000		
SLEEP - Go into Standby mode	1	00	0000	0110	0011	TO,PD	
SUBLW k Subtract W from literal	1	11	110x	kkkk	kkkk	C,DC,Z	
XORLW k Exclusive OR literal with W	1	11	1010	kkkk	kkkk	Z	

Note 1: When an I/O register is modified as a function of itself (e.g., MOVF GPIO, 1), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

**Note:** Additional information on the mid-range instruction set is available in the PIC® Mid-Range MCU Family Reference Manual (DS33023).

<sup>2:</sup> If this instruction is executed on the TMR0 register (and, where applicable, d = 1), the prescaler will be cleared if assigned to the Timer0 module.

<sup>3:</sup> If Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

### 10.2 Instruction Descriptions

ADDLW	Add Literal and W
Syntax:	[label] ADDLW k
Operands:	$0 \leq k \leq 255$
Operation:	$(W) + k \rightarrow (W)$
Status Affected:	C, DC, Z
Description:	The contents of the W register are added to the eight-bit literal 'k' and the result is placed in the W register.

BCF	Bit Clear f
Syntax:	[label] BCF f,b
Operands:	$\begin{array}{l} 0 \leq f \leq 127 \\ 0 \leq b \leq 7 \end{array}$
Operation:	$0 \rightarrow (f < b >)$
Status Affected:	None
Description:	Bit 'b' in register 'f' is cleared.

ADDWF	Add W and f
Syntax:	[label] ADDWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) + (f) $\rightarrow$ (destination)
Status Affected:	C, DC, Z
Description:	Add the contents of the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

BSF	Bit Set f
Syntax:	[/abe/] BSF f,b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$1 \rightarrow (f < b >)$
Status Affected:	None
Description:	Bit 'b' in register 'f' is set.

ANDLW	AND Literal with W
Syntax:	[label] ANDLW k
Operands:	$0 \leq k \leq 255$
Operation:	(W) .AND. (k) $\rightarrow$ (W)
Status Affected:	Z
Description:	The contents of W register are AND'ed with the eight-bit literal 'k'. The result is placed in the W register.

BTFSS	Bit Test f, Skip if Set
Syntax:	[/abe/] BTFSS f,b
Operands:	$0 \le f \le 127$ $0 \le b < 7$
Operation:	skip if (f <b>) = 1</b>
Status Affected:	None
Description:	If bit 'b' in register 'f' is '0', the next instruction is executed.  If bit 'b' is '1', then the next instruction is discarded and a NOP is executed instead, making this a 2Tcy instruction.

ANDWF	AND W with f
Syntax:	[/abe/] ANDWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .AND. (f) $\rightarrow$ (destination)
Status Affected:	Z
Description:	AND the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

BTFSC	Bit Test, Skip if Clear
Syntax:	[label] BTFSC f,b
Operands:	$\begin{array}{l} 0 \leq f \leq 127 \\ 0 \leq b \leq 7 \end{array}$
Operation:	skip if $(f < b >) = 0$
Status Affected:	None
Description:	If bit 'b' in register 'f' is '1', the next instruction is executed.  If bit 'b', in register 'f', is '0', the next instruction is discarded, and a NOP is executed instead, making this a 2Tcy instruction.

CALL	Call Subroutine
Syntax:	[label] CALL k
Operands:	$0 \leq k \leq 2047$
Operation:	(PC)+ 1 $\rightarrow$ TOS, k $\rightarrow$ PC<10:0>, (PCLATH<4:3>) $\rightarrow$ PC<12:11>
Status Affected:	None
Description:	Call Subroutine. First, return address (PC + 1) is pushed onto the stack. The eleven-bit immediate address is loaded into PC bits <10:0>. The upper bits of the PC are loaded from PCLATH. CALL is a two-cycle instruction.

CLRF	Clear f
Syntax:	[label] CLRF f
Operands:	$0 \leq f \leq 127$
Operation:	$00h \to (f)$ $1 \to Z$
Status Affected:	Z
Description:	The contents of register 'f' are cleared and the Z bit is set.

CLRW	Clear W
Syntax:	[label] CLRW
Operands:	None
Operation:	$00h \to (W)$ $1 \to Z$
Status Affected:	Z
Description:	W register is cleared. Zero bit (Z) is set.

CLRWDT	Clear Watchdog Timer
Syntax:	[label] CLRWDT
Operands:	None
Operation:	00h → WDT 0 → WDT prescaler, 1 → $\overline{TO}$ 1 → $\overline{PD}$
Status Affected:	TO, PD
Description:	CLRWDT instruction resets the Watchdog Timer. It also resets the prescaler of the WDT. Status bits TO and PD are set.

COMF	Complement f
Syntax:	[ label ] COMF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(\bar{f}) \rightarrow (destination)$
Status Affected:	Z
Description:	The contents of register 'f' are complemented. If 'd' is 0, the result is stored in W. If 'd' is 1, the result is stored back in register 'f'.

DECF	Decrement f
Syntax:	[label] DECF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (destination)
Status Affected:	Z
Description:	Decrement register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

DECFSZ	Decrement f, Skip if 0
Syntax:	[label] DECFSZ f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) - 1 $\rightarrow$ (destination); skip if result = 0
Status Affected:	None
Description:	The contents of register 'f' are decremented. If 'd' is $0$ , the result is placed in the W register. If 'd' is $1$ , the result is placed back in register 'f'. If the result is $1$ , the next instruction is executed. If the result is $0$ , then a NOP is executed instead, making it a 2TCY instruction.

INCFSZ	Increment f, Skip if 0
Syntax:	[ label ] INCFSZ f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) + 1 $\rightarrow$ (destination), skip if result = 0
Status Affected:	None
Description:	The contents of register 'f' are incremented. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.  If the result is 1, the next instruction is executed. If the result is 0, a NOP is executed instead, making it a 2Tcy instruction.

GOTO	Unconditional Branch
Syntax:	[label] GOTO k
Operands:	$0 \leq k \leq 2047$
Operation:	$k \rightarrow PC<10:0>$ PCLATH<4:3> $\rightarrow$ PC<12:11>
Status Affected:	None
Description:	GOTO is an unconditional branch. The eleven-bit immediate value is loaded into PC bits <10:0>. The upper bits of PC are loaded from PCLATH<4:3>. GOTO is a two-cycle instruction.

IORLW	Inclusive OR Literal with W
Syntax:	[label] IORLW k
Operands:	$0 \leq k \leq 255$
Operation:	(W) .OR. $k \rightarrow (W)$
Status Affected:	Z
Description:	The contents of the W register are OR'ed with the eight-bit literal 'k'. The result is placed in the W register.

INCF	Increment f
Syntax:	[label] INCF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) + 1 $\rightarrow$ (destination)
Status Affected:	Z
Description:	The contents of register 'f' are incremented. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.

IORWF	Inclusive OR W with f
Syntax:	[label] IORWF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .OR. (f) $\rightarrow$ (destination)
Status Affected:	Z
Description:	Inclusive OR the W register with register 'f'. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.

MOVF	Move f
Syntax:	[label] MOVF f,d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f) \rightarrow (dest)$
Status Affected:	Z
Description:	The contents of register f is moved to a destination dependent upon the status of d. If $d=0$ , the destination is W register. If $d=1$ , the destination is file register f itself. $d=1$ is useful to test a file register since status flag Z is affected.
Words:	1
Cycles:	1
Example:	MOVF FSR, 0
	After Instruction  W = value in FSR  register  Z = 1

MOVWF	Move W to f
Syntax:	[ label ] MOVWF f
Operands:	$0 \leq f \leq 127$
Operation:	$(W) \rightarrow (f)$
Status Affected:	None
Description:	Move data from W register to register 'f'.
Words:	1
Cycles:	1
Example:	MOVWF OPTION
	Before Instruction  OPTION = 0xFF  W = 0x4F  After Instruction  OPTION = 0x4F  W = 0x4F

MOVLW	Move literal to W
Syntax:	[label] MOVLW k
Operands:	$0 \leq k \leq 255$
Operation:	$k \rightarrow (W)$
Status Affected:	None
Description:	The eight-bit literal 'k' is loaded into W register. The "don't cares" will assemble as '0's.
Words:	1
Cycles:	1
Example:	MOVLW 0x5A
	After Instruction W = 0x5A

NOP	No Operation
Syntax:	[ label ] NOP
Operands:	None
Operation:	No operation
Status Affected:	None
Description:	No operation.
Words:	1
Cycles:	1
Example:	NOP

RETFIE	Return from Interrupt					
Syntax:	[label] RETFIE					
Operands:	None					
Operation:	$TOS \rightarrow PC$ , $1 \rightarrow GIE$					
Status Affected:	None					
Description:	Return from Interrupt. Stack is POPed and Top-of-Stack (TOS) is loaded in the PC. Interrupts are enabled by setting Global Interrupt Enable bit, GIE (INTCON<7>). This is a two-cycle instruction.					
Words:	1					
Cycles:	2					
Example:	RETFIE					
	After Interrupt PC = TOS GIE = 1					

RETLW	Return with literal in W						
Syntax:	[label] RETLW k						
Operands:	$0 \leq k \leq 255$						
Operation:	$k \rightarrow (W);$ TOS $\rightarrow$ PC						
Status Affected:	None						
Description:	The W register is loaded with the eight-bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two-cycle instruction.						
Words:	1						
Cycles:	2						
Example:	CALL TABLE;W contains table						
TABLE	<pre>;offset value • ;W now has table value •</pre>						
	ADDWF PCL;W = offset RETLW k1 ;Begin table RETLW k2 ; •						
	• RETLW kn ; End of table						
	Before Instruction  W = 0x07  After Instruction  W = value of k8						

RETURN	Return from Subroutine						
Syntax:	[label] RETURN						
Operands:	None						
Operation:	$TOS \rightarrow PC$						
Status Affected:	None						
Description:	Return from subroutine. The stack is POPed and the top of the stack (TOS) is loaded into the program counter. This is a two-cycle instruction.						

RLF	Rotate Left f through Carry					
Syntax:	[label] RLF f,d					
Operands:	$0 \le f \le 127$ $d \in [0,1]$					
Operation:	See description below					
Status Affected:	С					
Description:	The contents of register 'f' are rotated one bit to the left through the Carry Flag. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is stored back in register 'f'.					

RRF	Rotate Right f through Carry					
Syntax:	[label] RRF f,d					
Operands:	$0 \le f \le 127$ $d \in [0,1]$					
Operation:	See description below					
Status Affected:	С					
Description:	The contents of register 'f' are rotated one bit to the right through the Carry Flag. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed back in register 'f'.					

### SLEEP

Syntax:	[label] SLEEP		
Operands:	None		
Operation:	00h → WDT, 0 → WDT prescaler, 1 → $\overline{TO}$ , 0 → $\overline{PD}$		
Status Affected:	TO, PD		
Description:	The power-down Status bit, $\overline{PD}$ is cleared. Time-out Status bit, $\overline{TO}$ is set. Watchdog Timer and its prescaler are cleared. The processor is put into Sleep mode with the oscillator stopped.		

SUBLW	Subtract W from Literal					
Syntax:	[label] SUBLW k					
Operands:	$0 \leq k \leq 255$					
Operation:	$k - (W) \rightarrow (W)$					
Status Affected:	C, DC, Z					
Description:	The W register is subtracted (2's complement method) from the eight-bit literal 'k'. The result is placed in the W register.					

SUBWF	Subtract W from f					
Syntax:	[label] SUBWF f,d					
Operands:	$0 \le f \le 127$ $d \in [0,1]$					
Operation:	(f) - (W) $\rightarrow$ (destination)					
Status Affected:	C, DC, Z					
Description:	Subtract (2's complement method) W register from register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.					

SWAPF	Swap Nibbles in f				
Syntax:	[label] SWAPF f,d				
Operands:	$0 \le f \le 127$ $d \in [0,1]$				
Operation:	$(f<3:0>) \rightarrow (destination<7:4>),$ $(f<7:4>) \rightarrow (destination<3:0>)$				
Status Affected:	None				
Description:	The upper and lower nibbles of register 'f' are exchanged. If 'd' is 0, the result is placed in the W register. If 'd' is 1, the result is placed in register 'f'.				

XORLW	Exclusive OR Literal with W	XORWF	Exclusive OR W with f
Syntax:	[label] XORLW k	Syntax:	[/abe/] XORWF f,d
Operands:	$0 \leq k \leq 255$	Operands:	$0 \leq f \leq 127$
Operation:	(W) .XOR. $k \rightarrow (W)$		$d \in [0,1]$
Status Affected:	Z	Operation:	(W) .XOR. (f) $\rightarrow$ (destination)
Description:	The contents of the W register	Status Affected:	Z
<del>-</del>	are XOR'ed with the eight-bit literal 'k'. The result is placed in the W register.	Description:	Exclusive OR the contents of the W register with register 'f'. If 'd' is 0, the result is stored in the W register. If 'd' is 1, the result is stored back in register 'f'.

NOTES:

#### 11.0 DEVELOPMENT SUPPORT

The PIC® microcontrollers and dsPIC® digital signal controllers are supported with a full range of software and hardware development tools:

- · Integrated Development Environment
  - MPLAB® IDE Software
- · Compilers/Assemblers/Linkers
  - MPLAB C Compiler for Various Device Families
  - HI-TECH C for Various Device Families
  - MPASM™ Assembler
  - MPLINK<sup>™</sup> Object Linker/ MPLIB<sup>™</sup> Object Librarian
  - MPLAB Assembler/Linker/Librarian for Various Device Families
- · Simulators
  - MPLAB SIM Software Simulator
- · Emulators
  - MPLAB REAL ICE™ In-Circuit Emulator
- · In-Circuit Debuggers
  - MPLAB ICD 3
  - PICkit™ 3 Debug Express
- · Device Programmers
  - PICkit™ 2 Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration/Development Boards, Evaluation Kits, and Starter Kits

# 11.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16/32-bit microcontroller market. The MPLAB IDE is a Windows® operating system-based application that contains:

- · A single graphical interface to all debugging tools
  - Simulator
  - Programmer (sold separately)
  - In-Circuit Emulator (sold separately)
  - In-Circuit Debugger (sold separately)
- · A full-featured editor with color-coded context
- · A multiple project manager
- Customizable data windows with direct edit of contents
- · High-level source code debugging
- · Mouse over variable inspection
- Drag and drop variables from source to watch windows
- · Extensive on-line help
- Integration of select third party tools, such as IAR C Compilers

The MPLAB IDE allows you to:

- Edit your source files (either C or assembly)
- One-touch compile or assemble, and download to emulator and simulator tools (automatically updates all project information)
- · Debug using:
  - Source files (C or assembly)
  - Mixed C and assembly
  - Machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost-effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increased flexibility and power.

# 11.2 MPLAB C Compilers for Various Device Families

The MPLAB C Compiler code development systems are complete ANSI C compilers for Microchip's PIC18, PIC24 and PIC32 families of microcontrollers and the dsPIC30 and dsPIC33 families of digital signal controllers. These compilers provide powerful integration capabilities, superior code optimization and ease of

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

#### 11.3 HI-TECH C for Various Device Families

The HI-TECH C Compiler code development systems are complete ANSI C compilers for Microchip's PIC family of microcontrollers and the dsPIC family of digital signal controllers. These compilers provide powerful integration capabilities, omniscient code generation and ease of use.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

The compilers include a macro assembler, linker, preprocessor, and one-step driver, and can run on multiple platforms.

#### 11.4 MPASM Assembler

The MPASM Assembler is a full-featured, universal macro assembler for PIC10/12/16/18 MCUs.

The MPASM Assembler generates relocatable object files for the MPLINK Object Linker, Intel® standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM Assembler features include:

- Integration into MPLAB IDE projects
- User-defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

### 11.5 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK Object Linker combines relocatable objects created by the MPASM Assembler and the MPLAB C18 C Compiler. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB Object Librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

# 11.6 MPLAB Assembler, Linker and Librarian for Various Device Families

MPLAB Assembler produces relocatable machine code from symbolic assembly language for PIC24, PIC32 and dsPIC devices. MPLAB C Compiler uses the assembler to produce its object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- · Support for the entire device instruction set
- · Support for fixed-point and floating-point data
- Command line interface
- · Rich directive set
- · Flexible macro language
- · MPLAB IDE compatibility

#### 11.7 MPLAB SIM Software Simulator

The MPLAB SIM Software Simulator allows code development in a PC-hosted environment by simulating the PIC MCUs and dsPIC® DSCs on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a comprehensive stimulus controller. Registers can be logged to files for further run-time analysis. The trace buffer and logic analyzer display extend the power of the simulator to record and track program execution, actions on I/O, most peripherals and internal registers.

The MPLAB SIM Software Simulator fully supports symbolic debugging using the MPLAB C Compilers, and the MPASM and MPLAB Assemblers. The software simulator offers the flexibility to develop and debug code outside of the hardware laboratory environment, making it an excellent, economical software development tool.

### 11.8 MPLAB REAL ICE In-Circuit Emulator System

MPLAB REAL ICE In-Circuit Emulator System is Microchip's next generation high-speed emulator for Microchip Flash DSC and MCU devices. It debugs and programs PIC® Flash MCUs and dsPIC® Flash DSCs with the easy-to-use, powerful graphical user interface of the MPLAB Integrated Development Environment (IDE), included with each kit.

The emulator is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with either a connector compatible with incircuit debugger systems (RJ11) or with the new high-speed, noise tolerant, Low-Voltage Differential Signal (LVDS) interconnection (CAT5).

The emulator is field upgradable through future firmware downloads in MPLAB IDE. In upcoming releases of MPLAB IDE, new devices will be supported, and new features will be added. MPLAB REAL ICE offers significant advantages over competitive emulators including low-cost, full-speed emulation, run-time variable watches, trace analysis, complex breakpoints, a rugge-dized probe interface and long (up to three meters) interconnection cables.

# 11.9 MPLAB ICD 3 In-Circuit Debugger System

MPLAB ICD 3 In-Circuit Debugger System is Microchip's most cost effective high-speed hardware debugger/programmer for Microchip Flash Digital Signal Controller (DSC) and microcontroller (MCU) devices. It debugs and programs PIC® Flash microcontrollers and dsPIC® DSCs with the powerful, yet easy-to-use graphical user interface of MPLAB Integrated Development Environment (IDE).

The MPLAB ICD 3 In-Circuit Debugger probe is connected to the design engineer's PC using a high-speed USB 2.0 interface and is connected to the target with a connector compatible with the MPLAB ICD 2 or MPLAB REAL ICE systems (RJ-11). MPLAB ICD 3 supports all MPLAB ICD 2 headers.

# 11.10 PICkit 3 In-Circuit Debugger/ Programmer and PICkit 3 Debug Express

The MPLAB PICkit 3 allows debugging and programming of PIC® and dsPIC<sup>0</sup> Flash microcontrollers at a most affordable price point using the powerful graphical user interface of the MPLAB Integrated Development Environment (IDE). The MPLAB PICkit 3 is connected to the design engineer's PC using a full speed USB interface and can be connected to the target via an Microchip debug (RJ-11) connector (compatible with MPLAB ICD 3 and MPLAB REAL ICE). The connector uses two device I/O pins and the reset line to implement in-circuit debugging and In-Circuit Serial Programming™.

The PICkit 3 Debug Express include the PICkit 3, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

# 11.11 PICkit 2 Development Programmer/Debugger and PICkit 2 Debug Express

The PICkit™ 2 Development Programmer/Debugger is a low-cost development tool with an easy to use interface for programming and debugging Microchip's Flash families of microcontrollers. The full featured Windows® programming interface supports baseline (PIC10F, PIC12F5xx, PIC16F5xx), midrange (PIC12F6xx, PIC16F), PIC18F, PIC24, dsPIC30, dsPIC33, and PIC32 families of 8-bit, 16-bit, and 32-bit microcontrollers, and many Microchip Serial EEPROM products. With Microchip's powerful MPLAB Integrated Development Environment (IDE) the PICkit™ 2 enables in-circuit debugging on most PIC® microcontrollers. In-Circuit-Debugging runs, halts and single steps the program while the PIC microcontroller is embedded in the application. When halted at a breakpoint, the file registers can be examined and modified.

The PICkit 2 Debug Express include the PICkit 2, demo board and microcontroller, hookup cables and CDROM with user's guide, lessons, tutorial, compiler and MPLAB IDE software.

#### 11.12 MPLAB PM3 Device Programmer

The MPLAB PM3 Device Programmer is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular, detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 Device Programmer can read, verify and program PIC devices without a PC connection. It can also set code protection in this mode. The MPLAB PM3 connects to the host PC via an RS-232 or USB cable. The MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an MMC card for file storage and data applications.

# 11.13 Demonstration/Development Boards, Evaluation Kits, and Starter Kits

A wide variety of demonstration, development and evaluation boards for various PIC MCUs and dsPIC DSCs allows quick application development on fully functional systems. Most boards include prototyping areas for adding custom circuitry and provide application firmware and source code for examination and modification.

The boards support a variety of features, including LEDs, temperature sensors, switches, speakers, RS-232 interfaces, LCD displays, potentiometers and additional EEPROM memory.

The demonstration and development boards can be used in teaching environments, for prototyping custom circuits and for learning about various microcontroller applications.

In addition to the PICDEM™ and dsPICDEM™ demonstration/development board series of circuits, Microchip has a line of evaluation kits and demonstration software for analog filter design, KEELoQ® security ICs, CAN, IrDA®, PowerSmart battery management, SEEVAL® evaluation system, Sigma-Delta ADC, flow rate sensing, plus many more.

Also available are starter kits that contain everything needed to experience the specified device. This usually includes a single application and debug capability, all on one board.

Check the Microchip web page (www.microchip.com) for the complete list of demonstration, development and evaluation kits.

#### 12.0 ELECTRICAL SPECIFICATIONS

#### **Absolute Maximum Ratings†**

Ambient temperature under bias	40 to +125°C
Storage temperature	65°C to +150°C
Voltage on VDD with respect to Vss	0.3 to +6.5V
Voltage on MCLR with respect to Vss	0.3 to +13.5V
Voltage on all other pins with respect to Vss	0.3V to (VDD + 0.3V)
Total power dissipation <sup>(1)</sup>	800 mW
Maximum current out of Vss pin	300 mA
Maximum current into VDD pin	250 mA
Input clamp current, Iik (Vi < 0 or Vi > VDD)	± 20 mA
Output clamp current, lok (Vo < 0 or Vo >VDD)	± 20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by all GPIO	125 mA
Maximum current sourced all GPIO	125 mA

**Note 1:** Power dissipation is calculated as follows: PDIS = VDD x {IDD -  $\Sigma$  IOH} +  $\Sigma$  {(VDD-VOH) x IOH} +  $\Sigma$ (VOI x IOL).

**† NOTICE**: Stresses above those listed under 'Absolute Maximum Ratings' may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

**Note:** Voltage spikes below Vss at the  $\overline{\text{MCLR}}$  pin, inducing currents greater than 80 mA, <u>may</u> cause latch-up. Thus, a series resistor of 50-100  $\Omega$  should be used when applying a "low" level to the  $\overline{\text{MCLR}}$  pin, rather than pulling this pin directly to Vss.

FIGURE 12-1: PIC12F629/675 WITH A/D DISABLED VOLTAGE-FREQUENCY GRAPH, -40°C  $\leq$  Ta  $\leq$  +125°C




FIGURE 12-2: PIC12F675 WITH A/D ENABLED VOLTAGE-FREQUENCY GRAPH,  $-40^{\circ}C \le T_A \le +125^{\circ}C$ 





FIGURE 12-3: PIC12F675 WITH A/D ENABLED VOLTAGE-FREQUENCY GRAPH,  $0^{\circ}C \le T_A \le +125^{\circ}C$ 



### 12.1 DC Characteristics: PIC12F629/675-I (Industrial), PIC12F629/675-E (Extended)

DC CHA	ARACTE	Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{TA} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{TA} \le +125^{\circ}\text{C}$ for extended			10°C ≤ TA ≤ +85°C for industrial		
Param No.	Sym	Characteristic	Min	Min Typ† Max Units Conditions			
D001 D001A D001B D001C D001D	VDD	Supply Voltage	2.0 2.2 2.5 3.0 4.5	_ _ _ _	5.5 5.5 5.5 5.5 5.5	V V V V	Fosc < = 4 MHz: PIC12F629/675 with A/D off PIC12F675 with A/D on, 0°C to +125°C PIC12F675 with A/D on, -40°C to +125°C 4 MHz < Fosc < = 10 MHz
D002	VDR	RAM Data Retention Voltage <sup>(1)</sup>	1.5*	_		V	Device in Sleep mode
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal	_	Vss	_	V	See section on Power-on Reset for details
D004	SVDD	VDD Rise Rate to ensure internal Power-on Reset signal	0.05*	_	_	V/ms	See section on Power-on Reset for details
D005	VBOD		_	2.1	_	V	

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: This is the limit to which VDD can be lowered in Sleep mode without losing RAM data.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### 12.2 DC Characteristics: PIC12F629/675-I (Industrial)

			ard Ope	_			ss otherwise stated) +85°C for industrial
Param	Device Characteristics	Min	Typ+	Max	Units		Conditions
No.	Device Characteristics	IVIIII	Typ†	IVIAX	Ullits	<b>V</b> DD	Note
D010	Supply Current (IDD)	_	9	16	μΑ	2.0	Fosc = 32 kHz
		_	18	28	μΑ	3.0	LP Oscillator Mode
		_	35	54	μΑ	5.0	
D011		_	110	150	μΑ	2.0	Fosc = 1 MHz
		_	190	280	μΑ	3.0	XT Oscillator Mode
		_	330	450	μΑ	5.0	
D012		_	220	280	μΑ	2.0	Fosc = 4 MHz
		_	370	650	μΑ	3.0	XT Oscillator Mode
		_	0.6	1.4	mA	5.0	
D013		_	70	110	μΑ	2.0	Fosc = 1 MHz
		_	140	250	μΑ	3.0	EC Oscillator Mode
		_	260	390	μΑ	5.0	
D014		_	180	250	μΑ	2.0	Fosc = 4 MHz
		_	320	470	μΑ	3.0	EC Oscillator Mode
		_	580	850	μΑ	5.0	
D015		_	340	450	μΑ	2.0	Fosc = 4 MHz
		_	500	700	μΑ	3.0	INTOSC Mode
		_	0.8	1.1	mA	5.0	
D016		_	180	250	μΑ	2.0	Fosc = 4 MHz
		_	320	450	μΑ	3.0	EXTRC Mode
		_	580	800	μΑ	5.0	
D017		_	2.1	2.95	mA	4.5	Fosc = 20 MHz
			2.4	3.0	mA	5.0	HS Oscillator Mode

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**Note 1:** The test conditions for all IDD measurements in Active Operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT disabled.

<sup>2:</sup> The supply current is mainly a function of the operating voltage and frequency. Other factors such as I/O pin loading and switching rate, oscillator type, internal code execution pattern, and temperature also have an impact on the current consumption.

### 12.3 DC Characteristics: PIC12F629/675-I (Industrial)

			ard Oper ting temp			•	nless otherwise stated) A ≤ +85°C for industrial			
Param	Device Characteristics	Min	Typ†	Max	Units		Conditions			
No.	Device Characteristics	IVIIII	турі	IVIAX	Ullits	VDD	Note			
D020	Power-down Base Current	_	0.99	700	nA	2.0	WDT, BOD, Comparators, VREF,			
	(IPD)	_	1.2	770	nA	3.0	and T1OSC disabled			
		I	2.9	995	nA	5.0				
D021			0.3	1.5	μΑ	2.0	WDT Current <sup>(1)</sup>			
		ı	1.8	3.5	μΑ	3.0				
		_	8.4	17	μΑ	5.0				
D022		_	58	70	μΑ	3.0	BOD Current <sup>(1)</sup>			
		1	109	130	μΑ	5.0				
D023		I	3.3	6.5	μΑ	2.0	Comparator Current <sup>(1)</sup>			
			6.1	8.5	μΑ	3.0				
		ı	11.5	16	μΑ	5.0				
D024		I	58	70	μΑ	2.0	CVREF Current <sup>(1)</sup>			
			85	100	μΑ	3.0				
		ı	138	160	μΑ	5.0				
D025			4.0	6.5	μΑ	2.0	T1 Osc Current <sup>(1)</sup>			
		_	4.6	7.0	μΑ	3.0				
		_	6.0	10.5	μΑ	5.0				
D026		_	1.2	775	nA	3.0	A/D Current <sup>(1)</sup>			
		_	0.0022	1.0	μΑ	5.0				

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: The peripheral current is the sum of the base IDD or IPD and the additional current consumed when this peripheral is enabled. The peripheral  $\Delta$  current can be determined by subtracting the base IDD or IPD current from this limit. Max values should be used when calculating total current consumption.

<sup>2:</sup> The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD.

### 12.4 DC Characteristics: PIC12F629/675-E (Extended)

			ard Ope	_		•	ss otherwise stated) +125°C for extended
Param	Device Characteristics	Min	Tunt	Max	Units		Conditions
No.	Device Characteristics	IVIIII	Typ†	IVIAX	Units	<b>V</b> DD	Note
D010E	Supply Current (IDD)	_	9	16	μА	2.0	Fosc = 32 kHz
		_	18	28	μА	3.0	LP Oscillator Mode
		_	35	54	μА	5.0	
D011E		_	110	150	μΑ	2.0	Fosc = 1 MHz
		_	190	280	μΑ	3.0	XT Oscillator Mode
		_	330	450	μΑ	5.0	
D012E		_	220	280	μΑ	2.0	Fosc = 4 MHz
		_	370	650	μΑ	3.0	XT Oscillator Mode
		_	0.6	1.4	mA	5.0	
D013E		_	70	110	μΑ	2.0	Fosc = 1 MHz
		_	140	250	μΑ	3.0	EC Oscillator Mode
		_	260	390	μΑ	5.0	
D014E		_	180	250	μΑ	2.0	Fosc = 4 MHz
		_	320	470	μΑ	3.0	EC Oscillator Mode
		_	580	850	μΑ	5.0	
D015E		_	340	450	μА	2.0	Fosc = 4 MHz
			500	780	μΑ	3.0	INTOSC Mode
			8.0	1.1	mA	5.0	
D016E		_	180	250	μА	2.0	Fosc = 4 MHz
			320	450	μΑ	3.0	EXTRC Mode
		_	580	800	μА	5.0	
D017E			2.1	2.95	mA	4.5	Fosc = 20 MHz
		_	2.4	3.0	mA	5.0	HS Oscillator Mode

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**Note 1:** The test conditions for all IDD measurements in Active Operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD; MCLR = VDD; WDT disabled.

<sup>2:</sup> The supply current is mainly a function of the operating voltage and frequency. Other factors such as I/O pin loading and switching rate, oscillator type, internal code execution pattern, and temperature also have an impact on the current consumption.

#### 12.5 DC Characteristics: PIC12F629/675-E (Extended)

			ard Operat	_		•	otherwise stated) 25°C for extended
Param	Device Characteristics	Min	Typ†	Max	Units		Conditions
No.	Device Characteristics	IVIIII	турт	IVIAX	Units	<b>V</b> DD	Note
D020E	Power-down Base Current	_	0.00099	3.5	μА	2.0	WDT, BOD, Comparators, VREF,
	(IPD)		0.0012	4.0	μΑ	3.0	and T1OSC disabled
		-	0.0029	8.0	μΑ	5.0	
D021E		_	0.3	6.0	μΑ	2.0	WDT Current <sup>(1)</sup>
			1.8	9.0	μΑ	3.0	
		_	8.4	20	μΑ	5.0	
D022E			58	70	μΑ	3.0	BOD Current <sup>(1)</sup>
		l	109	130	μΑ	5.0	
D023E		_	3.3	10	μΑ	2.0	Comparator Current <sup>(1)</sup>
		_	6.1	13	μΑ	3.0	
		_	11.5	24	μΑ	5.0	
D024E		_	58	70	μΑ	2.0	CVREF Current <sup>(1)</sup>
		_	85	100	μΑ	3.0	
		_	138	165	μΑ	5.0	
D025E		_	4.0	10	μА	2.0	T1 Osc Current <sup>(1)</sup>
		_	4.6	12	μА	3.0	
		_	6.0	20	μА	5.0	
D026E		_	0.0012	6.0	μΑ	3.0	A/D Current <sup>(1)</sup>
		_	0.0022	8.5	μА	5.0	

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Note 1: The peripheral current is the sum of the base IDD or IPD and the additional current consumed when this peripheral is enabled. The peripheral  $\Delta$  current can be determined by subtracting the base IDD or IPD current from this limit. Max values should be used when calculating total current consumption.

<sup>2:</sup> The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD.

### 12.6 DC Characteristics: PIC12F629/675-I (Industrial), PIC12F629/675-E (Extended)

DC CHA	ARACT	ERISTICS			-40°C ≤ 7	ΓA ≤ +8	s otherwise stated) 5°C for industrial 25°C for extended
Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions
		Input Low Voltage					
	VIL	I/O ports					
D030		with TTL buffer	Vss	_	8.0	V	$4.5V \le VDD \le 5.5V$
D030A			Vss	_	0.15 VDD	V	Otherwise
D031		with Schmitt Trigger buffer	Vss	_	0.2 VDD	V	Entire range
D032		MCLR, OSC1 (RC mode)	Vss	_	0.2 VDD	V	
D033		OSC1 (XT and LP modes)	Vss	_	0.3	V	(Note 1)
D033A		OSC1 (HS mode)	Vss	_	0.3 VDD	V	(Note 1)
		Input High Voltage					
	VIH	I/O ports		_			
D040		with TTL buffer	2.0	_	Vdd	V	$4.5V \le VDD \le 5.5V$
D040A			(0.25 VDD+0.8)	_	Vdd	V	otherwise
D041		with Schmitt Trigger buffer	0.8 VDD	_	Vdd		entire range
D042		MCLR	0.8 VDD	_	Vdd	V	
D043		OSC1 (XT and LP modes)	1.6	_	VDD	V	(Note 1)
D043A		OSC1 (HS mode)	0.7 Vdd	_	VDD	V	(Note 1)
D043B		OSC1 (RC mode)	0.9 VDD	_	VDD	V	
D070	Ipur	<b>GPIO Weak Pull-up Current</b>	50*	250	400*	μА	VDD = 5.0V, VPIN = VSS
		Input Leakage Current <sup>(3)</sup>					
D060	lı∟	I/O ports	_	± 0.1	± 1	μА	VSS ≤ VPIN ≤ VDD, Pin at high-impedance
D060A		Analog inputs	_	± 0.1	± 1	μΑ	VSS ≤ VPIN ≤ VDD
D060B		VREF	_	± 0.1	± 1	μΑ	$Vss \le VPIN \le VDD$
D061		MCLR <sup>(2)</sup>	_	± 0.1	± 5	μ <b>A</b>	$Vss \le VPIN \le VDD$
D063		OSC1	_	± 0.1	± 5	μA	VSS ≤ VPIN ≤ VDD, XT, HS and LP osc configuration
		Output Low Voltage					
D080	Vol	I/O ports	_	_	0.6	V	IOL = 8.5 mA, VDD = 4.5V (Ind.)
D083		OSC2/CLKOUT (RC mode)	_	_	0.6	V	IOL = 1.6 mA, VDD = 4.5V (Ind.) IOL = 1.2 mA, VDD = 4.5V (Ext.)
		Output High Voltage					
D090	Vон	I/O ports	VDD - 0.7	_	_	V	IOH = -3.0 mA, VDD = 4.5V (Ind.)
D092		OSC2/CLKOUT (RC mode)	VDD - 0.7	_	_	>	IOH = -1.3 mA, VDD = 4.5V (Ind.) IOH = -1.0 mA, VDD = 4.5V (Ext.)

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

**Note 1:** In RC oscillator configuration, the OSC1/CLKIN pin is a Schmitt Trigger input. It is not recommended to use an external clock in RC mode.

<sup>2:</sup> The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

<sup>3:</sup> Negative current is defined as current sourced by the pin.

### 12.7 DC Characteristics: PIC12F629/675-I (Industrial), PIC12F629/675-E (Extended) (Cont.)

DC CHAR	ACTERI	STICS	Standard Operating Conditions (unless otherwise stated) Operating temperature $-40^{\circ}\text{C} \le \text{Ta} \le +85^{\circ}\text{C}$ for industrial $-40^{\circ}\text{C} \le \text{Ta} \le +125^{\circ}\text{C}$ for extended							
Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions			
		Capacitive Loading Specs on Output Pins								
D100	Cosc2	OSC2 pin	_	_	15*	pF	In XT, HS and LP modes when external clock is used to drive OSC1			
D101	Сю	io All I/O pins — 50* pf								
		Data EEPROM Memory								
D120	ED	Byte Endurance	100K	1M	_	E/W	-40°C ≤ TA ≤ +85°C			
D120A	ED	Byte Endurance	10K	100K		E/W	+85°C ≤ TA ≤ +125°C			
D121	VDRW	VDD for Read/Write	VMIN	_	5.5	V	Using EECON to read/write VMIN = Minimum operating voltage			
D122	TDEW	Erase/Write cycle time		5	6	ms				
D123	TRETD	Characteristic Retention	40	_	_	Year	Provided no other specifications are violated			
D124	TREF	Number of Total Erase/Write Cycles before Refresh <sup>(1)</sup>	1M	10M	_	E/W	-40°C ≤ TA ≤ +85°C			
		Program Flash Memory								
D130	EP	Cell Endurance	10K	100K	_	E/W	-40°C ≤ TA ≤ +85°C			
D130A	ED	Cell Endurance	1K	10K	_	E/W	+85°C ≤ TA ≤ +125°C			
D131	VPR	VDD for Read	VMIN	_	5.5	V	Vмім = Minimum operating voltage			
D132	VPEW	VDD for Erase/Write	4.5	_	5.5	V				
D133	TPEW	Erase/Write cycle time	_	2	2.5	ms				
D134	TRETD	Characteristic Retention	40	_	_	Year	Provided no other specifications are violated			

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: See Section 8.5.1 "Using the Data EEPROM" for additional information.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### 12.8 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created with one of the following formats:

- 1. TppS2ppS
- 2. TppS

Т			
F	Frequency	Т	Time
Lowerd	case letters (pp) and their meanings:		
рр			
СС	CCP1	osc	OSC1
ck	CLKOUT	rd	RD
cs	<del>CS</del>	rw	RD or WR
di	SDI	sc	SCK
do	SDO	ss	SS
dt	Data in	tO	T0CKI
io	I/O port	t1	T1CKI
mc	MCLR	wr	WR
Upperd	case letters and their meanings:		
S			
F	Fall	Р	Period
Н	High	R	Rise

٧

Z


Valid

High-Impedance

### FIGURE 12-4: LOAD CONDITIONS

Low

Invalid (High-Impedance)



### 12.9 AC CHARACTERISTICS: PIC12F629/675 (INDUSTRIAL, EXTENDED)

FIGURE 12-5: EXTERNAL CLOCK TIMING




TABLE 12-1: EXTERNAL CLOCK TIMING REQUIREMENTS

Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions
	Fosc	External CLKIN Frequency(1)	DC	_	37	kHz	LP Osc mode
			DC	_	4	MHz	XT mode
			DC	_	20	MHz	HS mode
			DC	_	20	MHz	EC mode
		Oscillator Frequency <sup>(1)</sup>	5	_	37	kHz	LP Osc mode
			_	4	_	MHz	INTOSC mode
			DC	_	4	MHz	RC Osc mode
			0.1	_	4	MHz	XT Osc mode
			1	_	20	MHz	HS Osc mode
1	Tosc	External CLKIN Period <sup>(1)</sup>	27	_	$\infty$	μS	LP Osc mode
			50	_	$\infty$	ns	HS Osc mode
			50	_	$\infty$	ns	EC Osc mode
			250		8	ns	XT Osc mode
		Oscillator Period <sup>(1)</sup>	27		200	μS	LP Osc mode
			_	250	_	ns	INTOSC mode
			250	_	_	ns	RC Osc mode
			250	_	10,000	ns	XT Osc mode
			50	_	1,000	ns	HS Osc mode
2	TCY	Instruction Cycle Time <sup>(1)</sup>	200	Tcy	DC	ns	Tcy = 4/Fosc
3	TosL,	External CLKIN (OSC1) High	2*	_	_	μS	LP oscillator, Tosc L/H duty cycle
	TosH	External CLKIN Low	20*	_	_	ns	HS oscillator, Tosc L/H duty
							cycle
			100 *		_	ns	XT oscillator, Tosc L/H duty cycle
4	TosR,	External CLKIN Rise	_	_	50*	ns	LP oscillator
	TosF	External CLKIN Fall	_	_	25*	ns	XT oscillator
			_	_	15*	ns	HS oscillator

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time-base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "min" values with an external clock applied to OSC1 pin. When an external clock input is used, the 'max' cycle time limit is "DC" (no clock) for all devices.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 12-2: PRECISION INTERNAL OSCILLATOR PARAMETERS

Param No.	Sym	Characteristic	Freq. Tolerance	Min	Typ†	Max	Units	Conditions
F10	Fosc	Internal Calibrated	±1	3.96	4.00	4.04	MHz	VDD = 3.5V, 25°C
		INTOSC Frequency	±2	3.92	4.00	4.08	MHz	$2.5V \le VDD \le 5.5V$ $0^{\circ}C \le TA \le +85^{\circ}C$
			±5	3.80	4.00	4.20	MHz	$2.0V \le VDD \le 5.5V$ - $40^{\circ}C \le TA \le +85^{\circ}C \text{ (IND)}$ - $40^{\circ}C \le TA \le +125^{\circ}C \text{ (EXT)}$
F14	Tioscst	Oscillator Wake-up from	_	_	6	8	μS	VDD = 2.0V, -40°C to +85°C
		Sleep start-up time*	_	_	4	6	μS	$VDD = 3.0V, -40^{\circ}C \text{ to } +85^{\circ}C$
			_	_	3	5	μS	$VDD = 5.0V, -40^{\circ}C \text{ to } +85^{\circ}C$

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 12-6: CLKOUT AND I/O TIMING




TABLE 12-3: CLKOUT AND I/O TIMING REQUIREMENTS

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
10	TosH2ckL	OSC1↑ to CLOUT↓		75	200	ns	(Note 1)
11	TosH2ckH	OSC1↑ to CLOUT↑	_	75	200	ns	(Note 1)
12	TckR	CLKOUT rise time	_	35	100	ns	(Note 1)
13	TckF	CLKOUT fall time	_	35	100	ns	(Note 1)
14	TckL2ioV	CLKOUT↓ to Port out valid	_	<u> </u>	20	ns	(Note 1)
15	TioV2ckH	Port in valid before CLKOUT↑	Tosc + 200 ns	_	_	ns	(Note 1)
16	TckH2iol	Port in hold after CLKOUT↑	0	<u> </u>	_	ns	(Note 1)
17	TosH2ioV	OSC1↑ (Q1 cycle) to Port out valid	_	50	150 *	ns	
			_	<u> </u>	300	ns	
18	TosH2ioI	OSC1↑ (Q2 cycle) to Port input invalid (I/O in hold time)	100	_	_	ns	
19	TioV2osH	Port input valid to OSC1↑ (I/O in setup time)	0	_	_	ns	
20	TioR	Port output rise time	_	10	40	ns	
21	TioF	Port output fall time	_	10	40	ns	
22	Tinp	INT pin high or low time	25	<u> </u>	_	ns	
23	Trbp	GPIO change INT high or low time	Tcy	_	_	ns	

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: Measurements are taken in RC mode where CLKOUT output is 4xTosc.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated.

FIGURE 12-7: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER AND POWER-UP TIMER TIMING




FIGURE 12-8: BROWN-OUT DETECT TIMING AND CHARACTERISTICS




TABLE 12-4: RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER, AND BROWN-OUT DETECT REQUIREMENTS

Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions
30	TMCL	MCLR Pulse Width (low)	2 TBD	— TBD	— TBD	μS ms	V <sub>DD</sub> = 5V, -40°C to +85°C Extended temperature
31	TWDT	Watchdog Timer Time-out Period (No Prescaler)	10 10	17 17	25 30	ms ms	VDD = 5V, -40°C to +85°C Extended temperature
32	Tost	Oscillation Start-up Timer Period	_	1024Tosc	_	_	Tosc = OSC1 period
33*	TPWRT	Power-up Timer Period	28* TBD	72 TBD	132* TBD	ms ms	V <sub>DD</sub> = 5V, -40°C to +85°C Extended Temperature
34	Tioz	I/O High-impedance from MCLR Low or Watchdog Timer Reset	_		2.0	μS	
	BVDD	Brown-out Detect Voltage	2.025	_	2.175	V	
		Brown-out Hysteresis	TBD	_	_		
35	TBOD	Brown-out Detect Pulse Width	100*	_	_	μS	$VDD \le BVDD (D005)$

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.




TABLE 12-5: TIMERO AND TIMER1 EXTERNAL CLOCK REQUIREMENTS

Param No.	Sym	С	haracteristic		Min	Тур†	Max	Units	Conditions
40*	Tt0H	T0CKI High Pulse	Width No Prescaler		0.5 Tcy + 20	_	_	ns	
				With Prescaler	10	_	-	ns	
41*	Tt0L	T0CKI Low Pulse	Width	No Prescaler	0.5 Tcy + 20	_	_	ns	
				With Prescaler	10	_	_	ns	
42*	Tt0P	T0CKI Period			Greater of: 20 or <u>Tcy + 40</u> N	_	-	ns	N = prescale value (2, 4,, 256)
45*	Tt1H	T1CKI High Time	Synchronous,	No Prescaler	0.5 Tcy + 20	_	_	ns	
			Synchronous, with Prescaler		15	_	_	ns	
			Asynchronous		30	_	_	ns	
46*	Tt1L	T1CKI Low Time	Synchronous,	No Prescaler	0.5 Tcy + 20	_	_	ns	
			Synchronous, with Prescaler		15	_	_	ns	
			Asynchronous		30	_	_	ns	
47*	Tt1P	T1CKI Input Period	Synchronous		Greater of: 30 or <u>Tcy + 40</u> N	_		ns	N = prescale value (1, 2, 4, 8)
			Asynchronous		60	_	_	ns	
	Ft1		nput frequency range by setting bit T10SCEN)		DC	_	200*	kHz	
48	TCKEZtmr1	Delay from externa	al clock edge to	timer increment	2 Tosc*	_	7 Tosc*	_	

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

TABLE 12-6: COMPARATOR SPECIFICATIONS

Comparator Specifications		Standard Operating Conditions -40°C to +125°C (unless otherwise stated)						
Sym	Characteristics	Min	Тур	Max	Units	Comments		
Vos	Input Offset Voltage	_	± 5.0	± 10	mV			
Vсм	Input Common Mode Voltage	0	_	VDD - 1.5	V			
CMRR	Common Mode Rejection Ratio	+55*	_		db			
Trt	Response Time <sup>(1)</sup>	_	150	400*	ns			
TMC2COV	Comparator Mode Change to Output Valid	_	_	10*	μS			

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** Response time measured with one comparator input at (VDD - 1.5)/2 while the other input transitions from Vss to VDD - 1.5V.

TABLE 12-7: COMPARATOR VOLTAGE REFERENCE SPECIFICATIONS

Voltage Reference Specifications		Standard Operating Conditions -40°C to +125°C (unless otherwise stated)						
Sym	Characteristics	Min Typ Max		Units	Comments			
	Resolution	_	VDD/24* VDD/32	_ _	LSb LSb	Low Range (VRR = 1) High Range (VRR = 0)		
	Absolute Accuracy	_	_	± 1/2 ± 1/2*	LSb LSb	Low Range (VRR = 1) High Range (VRR = 0)		
	Unit Resistor Value (R)	_	2k*		Ω			
	Settling Time <sup>(1)</sup>	_	_	10*	μS			

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** Settling time measured while VRR = 1 and VR<3:0> transitions from 0000 to 1111.

TABLE 12-8: PIC12F675 A/D CONVERTER CHARACTERISTICS:

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
A01	NR	Resolution	_	_	10 bits	bit	
A02	EABS	Total Absolute Error*	_	_	±1	LSb	VREF = 5.0V
A03	EIL	Integral Error	_	_	±1	LSb	VREF = 5.0V
A04	EDL	Differential Error	_	_	±1	LSb	No missing codes to 10 bits VREF = 5.0V
A05	EFS	Full Scale Range	2.2*	_	5.5*	V	
A06	Eoff	Offset Error	_	_	±1	LSb	VREF = 5.0V
A07	Egn	Gain Error	_	_	±1	LSb	VREF = 5.0V
A10	_	Monotonicity	_	guaranteed <sup>(3)</sup>	_	_	Vss ≤ Vain ≤ Vref+
A20 A20A	VREF	Reference Voltage	2.0 2.5	_	— VDD + 0.3	V	Absolute minimum to ensure 10-bit accuracy
A21	VREF	Reference V High (VDD or VREF)	Vss	_	VDD	V	
A25	VAIN	Analog Input Voltage	Vss	_	VREF	V	
A30	Zain	Recommended Impedance of Analog Voltage Source	_	_	10	kΩ	
A50	IREF	VREF Input Current <sup>(2)</sup>	10	_	1000	μΑ	During VAIN acquisition.  Based on differential of VHOLD to VAIN.
			_	_	10	μΑ	During A/D conversion cycle.

<sup>\*</sup> These parameters are characterized but not tested.

**Note 1:** When A/D is off, it will not consume any current other than leakage current. The power-down current spec includes any such leakage from the A/D module.

- 2: VREF current is from External VREF or VDD pin, whichever is selected as reference input.
- 3: The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

FIGURE 12-10: PIC12F675 A/D CONVERSION TIMING (NORMAL MODE)




TABLE 12-9: PIC12F675 A/D CONVERSION REQUIREMENTS

SLEEP instruction to be executed.


Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
130	TAD	A/D Clock Period	1.6	_	_	μS	Tosc based, VREF ≥ 3.0V
			3.0*	_	_	μS	Tosc based, VREF full range
130	TAD	A/D Internal RC Oscillator Period	3.0*	6.0	9.0*	μS	ADCS<1:0> = 11 (RC mode) At VDD = 2.5V
			2.0*	4.0	6.0*	μS	At VDD = 5.0V
131	TCNV	Conversion Time (not including Acquisition Time) <sup>(1)</sup>		11	_	TAD	Set GO bit to new data in A/D result register
132	TACQ	Acquisition Time	(Note 2)	11.5	_	μS	
			5*	-	_	μѕ	The minimum time is the amplifier settling time. This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 4.1 mV @ 4.096V) from the last sampled voltage (as stored on CHOLD).
134	Tgo	Q4 to A/D Clock Start	_	Tosc/2	_	_	If the A/D clock source is selected as RC, a time of TcY is added before the A/D clock starts. This allows the SLEEP instruction to be executed.

<sup>\*</sup> These parameters are characterized but not tested.

Note 1: ADRES register may be read on the following Tcy cycle.

2: See Section 7.1 "A/D Configuration and Operation" for minimum conditions.

<sup>†</sup> Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.



**FIGURE 12-11:** PIC12F675 A/D CONVERSION TIMING (SLEEP MODE)

#### TABLE 12-10: PIC12F675 A/D CONVERSION REQUIREMENTS (SLEEP MODE)

Param No.	Sym	Characteristic	Min	Typ†	Max	Units	Conditions
130	TAD	A/D Clock Period	1.6	_	_	μS	VREF ≥ 3.0V
			3.0*	_	_	μS	VREF full range
130	TAD	A/D Internal RC					ADCS<1:0> = 11 (RC mode)
		Oscillator Period	3.0*	6.0	9.0*	μS	At VDD = 2.5V
			2.0*	4.0	6.0*	μS	At VDD = 5.0V
131	TCNV	Conversion Time (not including Acquisition Time) <sup>(1)</sup>	1	11	1	TAD	
132	TACQ	Acquisition Time	(Note 2)	11.5	_	μS	
			5*	_		μ\$	The minimum time is the amplifier settling time. This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 4.1 mV @ 4.096V) from the last sampled voltage (as stored on CHOLD).
134	TGO	Q4 to A/D Clock Start	_	Tosc/2 + Tcy	_	_	If the A/D clock source is selected as RC, a time of Tcy is added before the A/D clock starts. This allows the SLEEP instruction to be executed.

These parameters are characterized but not tested.

Note 1: ADRES register may be read on the following Tcy cycle.

2: See Section 7.1 "A/D Configuration and Operation" for minimum conditions.

Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

NOTES:

#### 13.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES

The graphs and tables provided in this section are for design guidance and are not tested.

In some graphs or tables, the data presented are outside specified operating range (i.e., outside specified VDD range). This is for information only and devices are ensured to operate properly only within the specified range.

The data presented in this section is a statistical summary of data collected on units from different lots over a period of time and matrix samples. "Typical" represents the mean of the distribution at 25°C. "Max" or "min" represents (mean +  $3\sigma$ ) or (mean -  $3\sigma$ ) respectively, where  $\sigma$  is standard deviation, over the whole temperature range.

Typical Baseline IPD 6.0E-09 5.0E-09 4.0E-09 -40 3.0E-09 0 25 2.0E-09 1.0E-09 0.0E+00 2.5 3 3.5 4.5 5 5.5 VDD (V)

**FIGURE 13-1:** TYPICAL IPD vs. VDD OVER TEMP (-40°C TO +25°C)






FIGURE 13-3: TYPICAL IPD vs. VDD OVER TEMP (+125°C)







FIGURE 13-4: MAXIMUM IPD vs. VDD OVER TEMP (-40°C TO +25°C)




**FIGURE 13-5:** MAXIMUM IPD vs. VDD OVER TEMP (+85°C)








**FIGURE 13-7:** TYPICAL IPD WITH BOD ENABLED vs. VDD OVER TEMP (-40°C TO +125°C)



**FIGURE 13-8:** TYPICAL IPD WITH CMP ENABLED vs. VDD OVER TEMP (-40°C TO +125°C)



TYPICAL IPD WITH A/D ENABLED vs. VDD OVER TEMP (-40°C TO +25°C) FIGURE 13-9:





FIGURE 13-10: TYPICAL IPD WITH A/D ENABLED vs. VDD OVER TEMP (+85°C)



**FIGURE 13-11:** TYPICAL IPD WITH A/D ENABLED vs. VDD OVER TEMP (+125°C)





FIGURE 13-12: TYPICAL IPD WITH T1 OSC ENABLED vs. VDD OVER TEMP (-40°C TO +125°C), 32 kHZ, C1 AND C2=50 pF)



TYPICAL IPD WITH CVREF ENABLED vs. VDD OVER TEMP (-40°C TO +125°C) FIGURE 13-13:




FIGURE 13-14: TYPICAL IPD WITH WDT ENABLED vs. VDD OVER TEMP (-40°C TO +125°C)




FIGURE 13-15: MAXIMUM AND MINIMUM INTOSC FREQ vs. TEMPERATURE WITH  $0.1\mu F$  AND  $0.01\mu F$  DECOUPLING (VDD = 3.5V)






FIGURE 13-16: MAXIMUM AND MINIMUM INTOSC FREQ vs. VDD WITH  $0.1\mu F$  AND  $0.01\mu F$  DECOUPLING (+25°C)





NOTES:

#### 14.0 PACKAGING INFORMATION

#### 14.1 **Package Marking Information**

8-Lead PDIP (Skinny DIP)




Example

12F629-I /017 (e3) ○ **№** 0215

8-Lead SOIC



Example



8-Lead DFN-S




Example



8-Lead DFN (4x4 mm)



Example



Legend: XX...X Customer-specific information

> Year code (last digit of calendar year) ΥY Year code (last 2 digits of calendar year) WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code

(e3) Pb-free JEDEC designator for Matte Tin (Sn)

This package is Pb-free. The Pb-free JEDEC designator (@3)

can be found on the outer packaging for this package.


In the event the full Microchip part number cannot be marked on one line, it will Note: be carried over to the next line, thus limiting the number of available characters for customer-specific information.

#### 14.2 Package Details

The following sections give the technical details of the packages.

#### 8-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES	
	Dimension Limits	MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		.100 BSC	
Top to Seating Plane	A	_	_	.210
Molded Package Thickness	A2	.115	.130	.195
Base to Seating Plane	A1	.015	-	-
Shoulder to Shoulder Width	Е	.290	.310	.325
Molded Package Width	E1	.240	.250	.280
Overall Length	D	.348	.365	.400
Tip to Seating Plane	L	.115	.130	.150
Lead Thickness	С	.008	.010	.015
Upper Lead Width	b1	.040	.060	.070
Lower Lead Width	b	.014	.018	.022
Overall Row Spacing §	eB	_	_	.430

#### Notes:


- Pin 1 visual index feature may vary, but must be located with the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-018B

#### 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	;
D	imension Limits	MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		1.27 BSC	
Overall Height	А	_	_	1.75
Molded Package Thickness	A2	1.25	_	_
Standoff §	A1	0.10	_	0.25
Overall Width	E		6.00 BSC	
Molded Package Width	E1		3.90 BSC	
Overall Length	D		4.90 BSC	
Chamfer (optional)	h	0.25	_	0.50
Foot Length	L	0.40	_	1.27
Footprint	L1		1.04 REF	
Foot Angle	ф	0°	_	8°
Lead Thickness	С	0.17	_	0.25
Lead Width	b	0.31	_	0.51
Mold Draft Angle Top	α	5°	_	15°
Mold Draft Angle Bottom	β	5°	_	15°

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-057B

#### 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

	Units	N	<b>JILLIMETER</b>	S
Dimensio	n Limits	MIN	NOM	MAX
Contact Pitch	Е		1.27 BSC	
Contact Pad Spacing	С		5.40	
Contact Pad Width (X8)	X1			0.60
Contact Pad Length (X8)	Y1			1.55

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2057A

#### 8-Lead Plastic Dual Flat, No Lead Package (MF) – 6x5 mm Body [DFN-S]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		MILLIMETERS	3
	Dimension Limits	MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		1.27 BSC	
Overall Height	А	0.80	0.85	1.00
Standoff	A1	0.00	0.01	0.05
Contact Thickness	A3	0.20 REF		
Overall Length	D		5.00 BSC	
Overall Width	E		6.00 BSC	
Exposed Pad Length	D2	3.90	4.00	4.10
Exposed Pad Width	E2	2.20	2.30	2.40
Contact Width	b	0.35	0.40	0.48
Contact Length	L	0.50	0.60	0.75
Contact-to-Exposed Pad	K	0.20	_	_

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package may have one or more exposed tie bars at ends.
- 3. Package is saw singulated.
- 4. Dimensioning and tolerancing per ASME Y14.5M.


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.


Microchip Technology Drawing C04-122B

8-Lead Plastic Dual Flat, No Lead Package (MF) - 6x5 mm Body [DFN-S]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN



Units		N	<b>IILLIMETER</b>	S
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E		1.27 BSC	
Optional Center Pad Width	W2			2.40
Optional Center Pad Length	T2			4.10
Contact Pad Spacing	С		5.60	
Contact Pad Width (X8)	X1			0.45
Contact Pad Length (X8)	Y1			1.10

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2122A

#### 8-Lead Plastic Dual Flat, No Lead Package (MD) – 4x4x0.9 mm Body [DFN]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-131E Sheet 1 of 2

#### 8-Lead Plastic Dual Flat, No Lead Package (MD) – 4x4x0.9 mm Body [DFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		N	<b>IILLIMETER</b>	S
Dimension	Limits	MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		0.80 BSC	
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.00	0.02	0.05
Contact Thickness	A3		0.20 REF	
Overall Length	D		4.00 BSC	
Exposed Pad Width	E2	2.60	2.70	2.80
Overall Width	E		4.00 BSC	
Exposed Pad Length	D2	3.40	3.50	3.60
Contact Width	b	0.25	0.30	0.35
Contact Length	L	0.30	0.40	0.50
Contact-to-Exposed Pad	K	0.20	-	-

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package may have one or more exposed tie bars at ends.
- 3. Package is saw singulated
- 4. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-131E Sheet 2 of 2

#### 8-Lead Plastic Dual Flat, No Lead Package (MD) – 4x4x0.9 mm Body [DFN]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

Units		N	<b>IILLIMETER</b>	S
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E		0.80 BSC	
Optional Center Pad Width	W2			3.60
Optional Center Pad Length	T2			2.50
Contact Pad Spacing	C1		4.00	
Contact Pad Width (X8)	X1			0.35
Contact Pad Length (X8)	Y1			0.75
Distance Between Pads	G	0.45		

#### Notes:

1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2131B

NOTES:

# APPENDIX A: DATA SHEET REVISION HISTORY

#### **Revision A**

This is a new data sheet.

#### **Revision B**

Added characterization graphs.

Updated specifications.

Added notes to indicate Microchip programmers maintain all Calibration bits to factory settings and the PIC12F675 ANSEL register must be initialized to configure pins as digital I/O.

Updated MLF-S package name to DFN-S.

#### **Revision C**

#### **Revision D (01/2007)**

Updated Package Drawings; Replace PICmicro with PIC; Revised Product ID example (b).

#### **Revision E (03/2007)**

Replaced Package Drawings (Rev. AM); Replaced Development Support Section.

#### **Revision F (09/2009)**

Updated Registers to new format; Added information to the "Package Marking Information" (8-Lead DFN) and "Package Details" sections (8-Lead Dual Flat, No Lead Package (MD) 4X4X0.9 mm Body (DFN)); Added Land Patterns for SOIC (SN) and DFN-S (MF) packages; Updated Register 3-2; Added MD Package to the Product identification System chapter; Other minor corrections.

#### Revision G (03/2010)

Updated the Instruction Set Summary section, adding pages 76 and 77.

# APPENDIX B: DEVICE DIFFERENCES

The differences between the PIC12F629/675 devices listed in this data sheet are shown in Table B-1.

TABLE B-1: DEVICE DIFFERENCES

Feature	PIC12F629	PIC12F675
A/D	No	Yes

#### APPENDIX C: DEVICE MIGRATIONS

This section is intended to describe the functional and electrical specification differences when migrating between functionally similar devices (such as from a PIC16C74A to a PIC16C74B).

**Not Applicable** 

# APPENDIX D: MIGRATING FROM OTHER PIC® DEVICES

This discusses some of the issues in migrating from other PIC devices to the PIC12F6XX family of devices.

#### D.1 PIC12C67X to PIC12F6XX

TABLE 1: FEATURE COMPARISON

Feature	PIC12C67X	PIC12F6XX
Max Operating Speed	10 MHz	20 MHz
Max Program Memory	2048 bytes	1024 bytes
A/D Resolution	8-bit	10-bit
Data EEPROM	16 bytes	64 bytes
Oscillator Modes	5	8
Brown-out Detect	N	Y
Internal Pull-ups	GP0/1/3	GP0/1/2/4/5
Interrupt-on-change	GP0/1/3	GP0/1/2/3/4/5
Comparator	N	Y

Note: This device has been designed to perform to the parameters of its data sheet. It has been tested to an electrical specification designed to determine its conformance with these parameters. Due to process differences in the manufacture of this device, this device may have different performance characteristics than its earlier version. These differences may cause this device to perform differently in your application than the earlier version of this device.

Note: The user should verify that the device oscillator starts and performs as expected.

Adjusting the loading capacitor values and/ or the oscillator mode may be required.

INDEX		Interrupts	
A		Operation	
A/D	13	Operation During SLEEP	
Acquisition Requirements		Output	
Block Diagram		Reference	
Calculating Acquisition Time	47	Response Time	
Configuration and Operation		Comparator Specifications	
Effects of a RESET		Comparator Voltage Reference Specifications	
Internal Sampling Switch (Rss) Impedance		Configuration Bits	
Operation During SLEEP		Configuring the Voltage Reference	
PIC12F675 Converter Characteristics		Crystal Operation	
Source Impedance		Customer Change Notification Service	
Summary of Registers		Customer Notification Service	
Absolute Maximum Ratings		Customer Support	133
AC Characteristics	00	D	
Industrial and Extended	96	Data EEPROM Memory	
ADCON0		Associated Registers/Bits	52
A/D Control register (ADDRESS		Code Protection	
1Fh)	45	EEADR Register	49
Additional Pin Functions		EECON1 Register	
Interrupt-on-Change		EECON2 Register	
Weak Pull-up		EEDATA Register	
Analog Input Connection Considerations		Data Memory Organization	
Analog-to-Digital Converter. See A/D		DC Characteristics	
Assembler		Extended and Industrial	93
MPASM Assembler	82	Industrial	88
		Development Support	81
<b>B</b>		Device Differences	127
Block Diagram		Device Migrations	128
TMR0/WDT Prescaler	29	Device Overview	7
Block Diagrams		E	
Analog Input Mode			
Analog Input Model		EEADR — EEPROM Address Register (ADDRESS	40
Comparator Output		9Bh) EECON1 — EEPROM Control register (Address	49
Comparator Voltage Reference	41	_ ,	E0
GP0 and GP1 Pins		9Ch) EEPROM Data Memory	50
GP2		Reading	<b>5</b> 1
GP3		Spurious Write	
GP4		Write Verify	
GP5		Writing	
On-Chip Reset Circuit		Electrical Specifications	
RC Oscillator Mode		Errata	
Timer1			J
Watchdog Timer	67	F	
Brown-out	00	Firmware Instructions	71
Associated Registers		G	
Brown-out Detect (BOD)		General Purpose Register File	q
Brown-out Detect Timing and Characteristics	99	GPIO	
C		Associated Registers	27
C Compilers		GPIO — GPIO register (ADDRESS	
MPLAB C18		05H)	21
Calibrated Internal RC Frequencies	97	GPIO Port	
CLKOUT	56	GPIO, TRISIO Registers	
Code Examples		I	
Changing Prescaler	31	I	
Data EEPROM Read		ID Locations	
Data EEPROM Write	51	In-Circuit Debugger	
Initializing GPIO		In-Circuit Serial Programming	
Saving STATUS and W Registers in RAM	66	Indirect Addressing, INDF and FSR Registers	
Write Verify		Instruction Format	
Code Protection		Instruction Set	
Comparator		ADDLW	
Associated Registers		ADDWF	
Configuration		ANDLW	
Effects of a RESET		ANDWF	
I/O Operating Modes	39	MOVF	/6

BCF	73	Stack	19
BSF	73	Pin Descriptions and Diagrams	24
BTFSC	74	Pinout Descriptions	
BTFSS	73	PIC12F629	{
CALL	74	PIC12F675	
CLRF	74	Power Control/Status Register (PCON)	
CLRW	74	Power-Down Mode (SLEEP)	68
CLRWDT	74	Power-on Reset (POR)	58
COMF	74	Power-up Timer (PWRT)	58
DECF	74	Prescaler	3 <sup>-</sup>
DECFSZ	75	Switching Prescaler Assignment	3 <sup>-</sup>
GOTO	75	Program Memory Organization	
INCF	75	Programming, Device Instructions	
INCFSZ	75	R	
IORLW	75		_
IORWF		RC Oscillator	
MOVLW	76	Reader Response	
MOVWF		READ-MODIFY-WRITE OPERATIONS	7
NOP		Registers	
RETFIE		ANSEL (Analog Select)	
RETLW		CONFIG (Configuration Word)	
RETURN		EEADR (EEPROM Address)	
RLF		EECON1 (EEPROM Control)	5 <sup>-</sup>
RRF		EEDAT (EEPROM Data)	49
SLEEP		INTCON (Interrupt Control)	1
		IOCB (Interrupt-on-Change GPIO)	24
SUBLW		Maps	
SUBWF		PIC12F629	10
SWAPF		PIC12F675	10
XORLW		OPTION_REG (Option)	. 14, 30, 3
XORWF		OSCCAL (Oscillator Calibration)	
Summary Table		PCON (Power Control)	
nternal 4 MHz Oscillator		PIE1 (Peripheral Interrupt Enable 1)	
nternal Sampling Switch (Rss) Impedance		PIR1 (Peripheral Interrupt 1)	
nternet Address	133	STATUS	
nterrupts	63	T1CON (Timer1 Control)	
A/D Converter	65	VRCON (Voltage Reference Control)	
Comparator	65	WPU (Weak Pull-up)	
Context Saving		RESET	
GP2/INT	65	Revision History	
GPIO		•	12
Summary of Registers	66	S	
TMR0	65	Software Simulator (MPLAB SIM)	83
OC — INTERRUPT-ON-CHANGE GPIO register		Special Features of the CPU	53
ADDRESS 96h)	23	Special Function Registers	10
Л		Special Functions Registers Summary	1 <sup>,</sup>
ACL D	50	STATUS — STATUS Register (ADDRESS	
Access Occasionation	58	03h or 83h)	13
Memory Organization	40	Т	
Data EEPROM Memory			-
Aicrochip Internet Web Site		Time-out Sequence	
Aligrating from other PICmicro Devices		Timer0	
MPLAB ASM30 Assembler, Linker, Librarian		Associated Registers	
IPLAB Integrated Development Environment Softwar		External Clock	
MPLAB PM3 Device Programmer		Interrupt	
IPLAB REAL ICE In-Circuit Emulator System	83	Operation	29
IPLINK Object Linker/MPLIB Object Librarian	82	T0CKI	30
		Timer1	
PPCODE Field Descriptions	71	Associated Registers	
Oscillator Configurations		Asynchronous Counter Mode	
<u> </u>		Reading and Writing	
Oscillator Start-up Timer (OST)	30	Interrupt	
•		Modes of Operations	
Packaging	117	Operation During SLEEP	
Details		Oscillator	
Marking		Prescaler	
PCL and PCLATH		Timer1 Module with Gate Control	
Computed GOTO		Timing Diagrams	
	-	5 5	

CLKOUT and I/O	98
External Clock	96
INT Pin Interrupt	65
PIC12F675 A/D Conversion (Normal Mode)	104
PIC12F675 A/D Conversion Timing	
(SLEEP Mode)	105
RESET, Watchdog Timer, Oscillator Start-up Time	
and Power-up Timer	99
Time-out Sequence on Power-up (MCLR not Tied	
VDD)/	
Case 1	62
Case 2	62
Time-out Sequence on Power-up	
(MCLR Tied to VDD)	62
Timer0 and Timer1 External Clock	101
Timer1 Incrementing Edge	33
Timing Parameter Symbology	95
TRISIO — GPIO Tri-state REGISTER (Address	
85H)	22
V	
Voltage Reference Accuracy/Error	41
w	
Watchdog Timer	67
Summary of Registers	
, ,	00
WPU — Weak pull-up Register (ADDRESS 95h)	22
WWW Address	
WWW On-Line Support	

NOTES:

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com, click on Customer Change Notification and follow the registration instructions.

#### **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- · Technical Support
- · Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://support.microchip.com

#### **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

10:	Technical Publications Manager	Total Pages Sent				
RE:	Reader Response					
Fror	n: Name					
	Company					
	Address					
	City / State / ZIP / Country					
	Telephone: ()	FAX: ()				
	lication (optional):					
Wou	ıld you like a reply?YN					
Dev	ice: PIC12F629/675	Literature Number: DS41190G				
Que	estions:					
1.	What are the best features of this document?					
2	Llow does this decument most your h	ordusers and aeffuers development peeds?				
۷.	now does this document meet your n	ardware and software development needs?				
3.	Do you find the organization of this document easy to follow? If not, why?					
4.	What additions to the document do yo	ou think would enhance the structure and subject?				
•						
5.	What deletions from the document could be made without affecting the overall usefulness?					
6.	Is there any incorrect or misleading in	formation (what and where)?				
7	Llow would you impresse this do					
7.	How would you improve this documer	u.;				
•						

#### PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO.	x /xx xxx	Exa	mples:
Device	Temperature Package Pattern Range	a) b)	PIC12F629 - E/P 301 = Extended Temp., PDIP package, 20 MHz, QTP pattern #301. PIC12F675 - I/SN = Industrial temp., SOIC package, 20 MHz.
Device:	PIC12F6XX: Standard VDD range PIC12F6XXT: (Tape and Reel)		
Temperature Range:	I = $-40$ °C to $+85$ °C (Industrial) E = $-40$ °C to $+125$ °C (Extended)		
Package:	P = PDIP SN = SOIC (Gull wing, 3.90 mm body) MF = MLF-S MD = 8-Lead Plastic Dual Flat, No Lead (4X4) (DFN)		
Pattern:	ern: 3-Digit Pattern Code for QTP (blank otherwise)		

<sup>\*</sup> JW Devices are UV erasable and can be programmed to any device configuration. JW Devices meet the electrical requirement of each oscillator type.



### WORLDWIDE SALES AND SERVICE

#### **AMERICAS**

**Corporate Office** 

2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://support.microchip.com

Web Address: www.microchip.com

Atlanta

Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

**Boston** 

Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

Chicago Itasca, IL

Tel: 630-285-0071 Fax: 630-285-0075

Cleveland

Independence, OH Tel: 216-447-0464 Fax: 216-447-0643

**Dallas** 

Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

**Detroit** 

Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

Kokomo

Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles

Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara

Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

**Toronto** 

Mississauga, Ontario, Canada

Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Asia Pacific Office Suites 3707-14, 37th Floor

Tower 6, The Gateway Harbour City, Kowloon Hong Kong

Tel: 852-2401-1200 Fax: 852-2401-3431

Australia - Sydney

Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

China - Beijing

Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

China - Chengdu

Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

China - Chongqing

Tel: 86-23-8980-9588 Fax: 86-23-8980-9500

China - Hong Kong SAR

Tel: 852-2401-1200 Fax: 852-2401-3431

China - Nanjing

Tel: 86-25-8473-2460 Fax: 86-25-8473-2470

China - Qingdao

Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

China - Shanghai

Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

China - Shenyang

Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

China - Shenzhen

Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

China - Wuhan

Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

China - Xian

Tel: 86-29-8833-7252 Fax: 86-29-8833-7256

China - Xiamen

Tel: 86-592-2388138 Fax: 86-592-2388130

China - Zhuhai

Tel: 86-756-3210040 Fax: 86-756-3210049

#### ASIA/PACIFIC

India - Bangalore Tel: 91-80-3090-4444

Fax: 91-80-3090-4123

India - New Delhi

Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune

Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

Japan - Yokohama

Tel: 81-45-471- 6166 Fax: 81-45-471-6122

Korea - Daegu

Tel: 82-53-744-4301 Fax: 82-53-744-4302

Korea - Seoul

Tel: 82-2-554-7200 Fax: 82-2-558-5932 or

82-2-558-5934

Malaysia - Kuala Lumpur

Tel: 60-3-6201-9857 Fax: 60-3-6201-9859

Malaysia - Penang

Tel: 60-4-227-8870 Fax: 60-4-227-4068

Philippines - Manila

Tel: 63-2-634-9065 Fax: 63-2-634-9069

**Singapore** 

Tel: 65-6334-8870 Fax: 65-6334-8850

Taiwan - Hsin Chu

Tel: 886-3-6578-300 Fax: 886-3-6578-370

Taiwan - Kaohsiung

Tel: 886-7-536-4818 Fax: 886-7-536-4803

Taiwan - Taipei

Tel: 886-2-2500-6610 Fax: 886-2-2508-0102 Thailand - Bangkok

Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### **EUROPE**

Austria - Wels

Tel: 43-7242-2244-39 Fax: 43-7242-2244-393

Denmark - Copenhagen

Tel: 45-4450-2828 Fax: 45-4485-2829

France - Paris

Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

Germany - Munich

Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

Italy - Milan

Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen

Tel: 31-416-690399 Fax: 31-416-690340

Spain - Madrid

. Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** 

Tel: 44-118-921-5869 Fax: 44-118-921-5820

01/05/10